

AD-A105 797

BAKER (MICHAEL) JR INC BEAVER PA
NATIONAL DAM SAFETY PROGRAM. HONK FALLS DAM (INVENTORY NUMBER N--ETC(U)
AUG 81 G KESTER DACW51-81-C-0010


F/G 13/13

DACW51-81-C-0010

UNCLASSIFIED

NL

1 of 2
AD-A105 797



AD A105797

LOWER HUDSON RIVER BASIN


HONK FALLS DAM

ULSTER COUNTY, NEW YORK
INVENTORY NO. N.Y. 73




LEVEL II

PHASE I INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



DTIC FILE COPY

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED



NEW YORK DISTRICT CORPS OF ENGINEERS

AUGUST 1981

10 10 19

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A105	299
4. TITLE (and Subtitle) Phase I Inspection Report Honk Falls Dam Lower Hudson River Basin, Ulster County, NY Inventory No. 73		5. TYPE OF REPORT & PERIOD COVERED Phase I Inspection Report National Dam Safety Program
7. AUTHOR(s) GRANVILLE/KESTER, JR.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Michael Baker, Jr. Inc. 4301 Dutch Ridge Road Box 280 Beaver, PA 15009		8. CONTRACT OR GRANT NUMBER(s) DACW51-81-C-0010
11. CONTROLLING OFFICE NAME AND ADDRESS Department of the Army 26 Federal Plaza New York District, CofE New York, New York. 10287		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS 1111
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Department of the Army 26 Federal Plaza New York District, CofE New York, NY 10287		12. REPORT DATE 14 August 1981
15. DISTRIBUTION STATEMENT (of this Report) Approved for public release; Distribution unlimited.		13. NUMBER OF PAGES
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		15. SECURITY CLASS. (of this report) UNCLASSIFIED
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety National Dam Safety Program Visual Inspection Hydrology, Structural Stability Honk Falls Dam Ulster County Lower Hudson River Basin		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report provides information and analysis on the physical condition of the dam as of the report date. Information and analysis are based on visual inspection of the dam by the performing organization. Examination of available documents and a visual inspection of the dam and appurtenant structures did not reveal conditions which constitute an immediate hazard to human life or property.		

Using the Corps of Engineers' screening criteria, it has been determined that the dam would be overtopped for all storms exceeding approximately 26 percent of the Probable Maximum Flood (PMF). The spillway is, therefore, adjudged as "seriously inadequate" and the dam is assessed as "unsafe, non-emergency."

The classification of "unsafe" means that, based on an initial screening and preliminary computations, there appears to be a serious deficiency in spillway capacity, so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard to loss of life downstream.

Structural stability analyses based on available information indicate that factors of safety against overturning and sliding are low for all conditions analyzed. When the dam is subjected to severe loading conditions such as ice loading or water levels overtopping the dam, the factors of safety are below recommended levels.

Therefore, a detailed stability analysis is considered necessary to determine actual stability conditions of the dam.

It is therefore recommended that, within three months of notification of the owner, detailed hydrologic and hydraulic investigations of the structure should be undertaken to more accurately determine the site-specific characteristics of the watershed and their effects upon the overtopping potential of the dam. At the same time, further analyses of structural stability of the overflow and nonoverflow sections should be performed. The results of these investigations and analyses will determine the appropriate remedial measures which will be required. In the interim, a detailed emergency action plan must be developed and implemented during periods of unusually heavy precipitation. Also, around-the-clock surveillance must be provided during these periods.

At the present time, there exists no inspection or maintenance program at the dam. A program of regular inspection and maintenance should be established. The dam should be examined for seeps when the reservoir is below the spillway crest.

Accession For	
NTIS GRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Avail and/or	
Dist	Special
A	

DTIC
SELECTE
OCT 20 1981
D

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through frequent inspections can unsafe conditions be detected and only through continued care and maintenance can these conditions be prevented or corrected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
HONK FALLS DAM
I.D. No. NY 73
DEC DAM No. 177C-735 LOWER HUDSON RIVER BASIN
ULSTER COUNTY, NEW YORK

TABLE OF CONTENTS

	<u>PAGE NO.</u>
- ASSESSMENT	-
- OVERVIEW PHOTOGRAPH	-
1 PROJECT INFORMATION	1
1.1 GENERAL	1
1.2 DESCRIPTION OF PROJECT	1
1.3 PERTINENT DATA	2
2 ENGINEERING DATA	5
2.1 GEOLOGY	5
2.2 SUBSURFACE INVESTIGATION	5
2.3 DAM AND APPURTENANT STRUCTURES	5
2.4 CONSTRUCTION RECORDS	6
2.5 OPERATION RECORDS	6
2.6 EVALUATION OF DATA	6
3 VISUAL INSPECTION	7
3.1 FINDINGS	7
3.2 EVALUATION	8
4 OPERATION AND MAINTENANCE PROCEDURES	11
4.1 PROCEDURES	11
4.2 MAINTENANCE OF THE DAM	11
4.3 WARNING SYSTEM	11
4.4 EVALUATION	11
5 HYDRAULIC/HYDROLOGIC	13
5.1 DRAINAGE AREA CHARACTERISTICS	13
5.2 ANALYSIS CRITERIA	13
5.3 SPILLWAY CAPACITY	13
5.4 RESERVOIR CAPACITY	13
5.5 FLOODS OF RECORD	14
5.6 OVERTOPPING POTENTIAL	14
5.7 RESERVOIR EMPTYING POTENTIAL	14
5.8 EVALUATION	14

	<u>PAGE NO.</u>
6 STRUCTURAL STABILITY	15
6.1 EVALUATION OF STRUCTURAL STABILITY	15
6.2 STABILITY ANALYSIS	16
6.3 SEISMIC STABILITY	17
7 ASSESSMENT/RECOMMENDATIONS	19
7.1 ASSESSMENT	19
7.2 RECOMMENDED MEASURES	20

APPENDIX

- A. PHOTOGRAPHS
- B. VISUAL INSPECTION CHECKLIST
- C. HYDROLOGIC/HYDRAULIC DATA AND COMPUTATIONS
- D. REFERENCES
- E. DRAWINGS
- F. BACKGROUND DOCUMENTS
- G. STRUCTURAL STABILITY

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Honk Falls Dam (I.D. No. NY 73)
State: New York
County: Ulster
Stream: Rondout Creek
Date of Inspection: 8 March 1981

ASSESSMENT

Examination of available documents and a visual inspection of the dam and appurtenant structures did not reveal conditions which constitute an immediate hazard to human life or property.

Using the Corps of Engineers' screening criteria, it has been determined that the dam would be overtopped for all storms exceeding approximately 26 percent of the Probable Maximum Flood (PMF). The spillway is, therefore, adjudged as "seriously inadequate" and the dam is assessed as "unsafe, non-emergency."

The classification of "unsafe" means that, based on an initial screening and preliminary computations, there appears to be a serious deficiency in spillway capacity, so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard to loss of life downstream.

Structural stability analyses based on available information indicate that factors of safety against overturning and sliding are low for all conditions analyzed. When the dam is subjected to severe loading conditions such as ice loading or water levels overtopping the dam, the factors of safety are below recommended levels.

Therefore, a detailed stability analysis is considered necessary to determine actual stability conditions of the dam.

It is therefore recommended that, within three months of notification of the owner, detailed hydrologic and hydraulic investigations of the structure should be undertaken to more accurately determine the site-specific characteristics

of the watershed and their effects upon the overtopping potential of the dam. At the same time, further analyses of the structural stability of the overflow and nonoverflow sections should be performed. The results of these investigations and analyses will determine the appropriate remedial measures which will be required. In the interim, a detailed emergency action plan must be developed and implemented during periods of unusually heavy precipitation. Also, around-the-clock surveillance must be provided during these periods.

At the present time, there exists no inspection or maintenance program at the dam. A program of regular inspection and maintenance should be established. The dam should be examined for seeps when the reservoir is below the spillway crest.

The following remedial measures must be completed within one year:

1. The gates on the outlet pipes should be repaired, and their controls should be made operable.
2. Determine the source of and repair the area of seepage at the soil-concrete contact along the right wall.
3. Determine the source of and repair the area of seepage at the left wingwall.
4. Determine the cause of and repair the seepage below the auxiliary spillways.
5. Repair the eroded areas at the toe of the dam and at the construction joints.
6. Repair all areas on the dam where the concrete is spalled and deteriorated.
7. Remove all brush and trees growing near the right abutment and on the dam.
8. Remove the trees and debris from the channel below the auxiliary spillways.
9. A program of periodic inspections and maintenance of the dam should be established. All inspections and maintenance should be recorded for future reference.
10. A staff gage should be installed to monitor reservoir levels above normal pool.

SUBMITTED:

Granville Kester
Granville Kester, Jr., P.E.
Vice President
MICHAEL BAKER, JR. of New York, INC.

APPROVED:

W.M. Smith, Jr.
Colonel W.M. Smith, Jr.
New York District Engineer

DATE:

14 Aug 81



Overall View of Dam
Honk Falls Dam
I.D. No. NY 73
8 March 1981

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM
HONK FALLS DAM
I.D. No. NY 73
DEC DAM No. 177C-735
LOWER HUDSON RIVER BASIN
ULSTER COUNTY, NEW YORK

SECTION 1: PROJECT INFORMATION

1.1 GENERAL

- a. Authority - The Phase I inspection reported herein was authorized by the Department of the Army, New York District, Corps of Engineers, to fulfill the requirements of the National Dam Inspection Act, Public Law 92-367.
- b. Purpose of Inspection - This inspection was conducted to evaluate the existing conditions of the dam, to identify deficiencies and hazardous conditions, to determine if these deficiencies constitute hazards to life and property, and to recommend remedial measures where required.

1.2 DESCRIPTION OF PROJECT

- a. Description of Dam - Honk Falls Dam is a concrete gravity structure 42.2 feet high, measured from the crest to the toe of the dam, and 294 feet long. The overflow section (principal spillway) is located in the center of the dam and consists of a 190.5-foot long broad-crested weir with a vertical upstream face and a sloping downstream face. The auxiliary spillway, located to the right of the principal spillway, has a total length of 22.3 feet and consists of a broad-crested concrete weir with vertical upstream and downstream faces. The non-overflow sections are 20 feet long on the left side and 61.2 feet long on the right side of the dam. Beneath the auxiliary spillways are two 6-foot diameter outlet pipes. A 3-foot diameter outlet pipe and a 12-inch outlet pipe are below the right and left sides of the spillway, respectively.
- b. Location - Honk Falls Dam is located on Rondout Creek, a tributary of the Hudson River, 3 miles north of Ellenville, New York. The reservoir and dam are in Ulster County, New York. The coordinates

of the dam are N 41° 45' and W 74° 22.9'. The dam can be found on the Rondout Reservoir and Ellenville, New York, USGS 7.5 minute topographic quadrangles. A Location Map is shown in Appendix E.

- c. Size Classification - Honk Falls Dam is 42.2 feet high, and the reservoir storage capacity at the minimum top of dam (elevation 579.1 feet T.B.M.) is 1504 acre-feet. Therefore, the dam is in the "intermediate" size category as defined by the Recommended Guidelines for Safety Inspection of Dams (Reference 13, Appendix D).
- d. Hazard Classification - One home is 1700 feet downstream from the dam. Napanoch, New York, is 6000 feet downstream from the dam. Loss of life in the home and Napanoch is likely if the dam were to fail. Honk Falls Dam is therefore considered in the "high" hazard category as defined by the Recommended Guidelines for Safety Inspection of Dams.
- e. Ownership - The dam and reservoir are owned by Recycled Paper Corp., c/o Albert I. Lonstein, Route 209, Terrace Hill, Ellenville, New York 12428.
- f. Purpose of the Dam - Honk Lake is used for recreation.
- g. Design and Construction - The dam was built about 1898. The designer and contractor are unknown.
- h. Normal Operating Procedures - The reservoir is typically maintained at the spillway crest. There has been no maintenance or inspection of the dam for the past few years.

1.3 PERTINENT DATA

a.	<u>Drainage Area (square miles)</u> -	104.09
b.	<u>Discharge at Dam (c.f.s.)</u>	
	Spillway Capacity (at Minimum Top of Dam Elev. 579.1 ft. M.S.L.)	20,119.0
c.	<u>Elevation (Feet Above M.S.L.)¹ -</u>	
	Minimum Top of Dam	579.1
	Normal Pool (Spillway Crest)	569.0
	Streambed at Toe of Dam	536.9

¹All elevations are referenced to the spillway crest, elev. 569.0 ft. M.S.L., estimated from the USGS 7.5 minute topographic quadrangle, Rondout Reservoir, NY.

d. Reservoir Surface (Acres) -

Top of Dam (Elev. 579.1 ft. M.S.L.)	86.2
Spillway Crest (Elev. 569.0 ft. M.S.L.)	44.1

e. Reservoir Storage Capacity (Acre-Feet) -

Top of Dam (Elev. 579.1 ft. M.S.L.)	1504.0
Spillway Crest (Elev. 569.0 ft. M.S.L.)	860.0

f. Dam -

Type: Concrete gravity	
Length (Feet)	294.0
Height (Feet)	42.2
Top Width (Feet)	2.5
Side Slopes - Upstream	Vertical
Downstream	1V:1.3H

g. Principal Spillway -

Type: Concrete broad-crested weir	
Crest Length Perpendicular to Flow (Feet)	190.5
Crest Width Parallel to Flow (Feet)	3.6
Crest Elevation (Feet M.S.L.)	569.0

h. Auxiliary Spillway -

Type: Concrete broad-crested weir	
Total Crest Length Perpendicular to Flow (Feet)	22.3
Crest Width Parallel to Flow (Feet)	0.8
Crest Elevation (Feet M.S.L.)	576.6

i. Reservoir Drain -

Type: Two 6-foot diameter pipes, 15.4 feet below the spillway crest, with inoperative wooden gates. One 3-foot diameter pipe, 28.1 feet below the spillway crest, that appears to be plugged. One 12-inch cast iron pipe, 30.1 feet below the spillway crest, with a gate valve.

SECTION 2: ENGINEERING DATA

2.1 GEOLOGY

Honk Falls Dam is located along the western margin of the Rondout-Escopus Valley region, Valley and Ridge physiographic province - Hudson Lowland area. Bedrock in this region consists of faulted and folded Devonian and Silurian limestones, shales, and sandstones. Typical topographic relief in the region is 500 feet.

The Geologic Map of New York (Reference 2, Appendix D) indicates that bedrock units in the immediate vicinity of the dam are shales and siltstones of the undifferentiated Hamilton Group, Middle Devonian System. Outcrops of these units occur at the dam site.

The bedrock surface of Ulster County has been modified by the action of continental glaciation; therefore, most of the county is blanketed by ground moraine deposits.

There do not appear to be any geologic faults in the dam or reservoir area.

2.2 SUBSURFACE INVESTIGATION

No site-specific subsurface information was available for review by this investigation. However, as shown on the Field Sketch in Appendix E, extensive outcrops of steeply dipping bedrock are located immediately downstream from the dam. It can be assumed with a high degree of confidence therefore, that the dam is constructed primarily on bedrock.

The Soil Survey of Ulster County, New York (Reference 3, Appendix E) classifies the soil in the valley below the dam in the Arnot-Oquaga-Rock outcrop complex. These bouldery soils occur on steep slopes and are moderately to excessively well-drained loams with thickness up to 26 inches. They are said to be moderately permeable and with very rapid runoff characteristics. Free water, except for brief periods in spring and after heavy rain, is generally below the bedrock surface.

2.3 DAM AND APPURTENANT STRUCTURES

Honk Falls Dam was originally built around 1898 to provide power for a paper mill. Presently, the dam is

used for recreation purposes only. The dam is a concrete gravity dam approximately 42 feet high and 294 feet long. The dam has a 190.5-foot long main spillway which begins 20 feet from the left¹ abutment. It also has two auxiliary spillways on the right side of the dam. Beneath the auxiliary spillways are two 6-foot diameter outlet pipes. There is a 12-inch outlet pipe under the left side of the main spillway and a 3-foot diameter pipe under the right side. It appears that the dam is founded on bedrock, at least under the main spillway section. The auxiliary spillway and the right abutment for the dam may be founded on bedrock or soil.

The existing dam is illustrated by a field sketch which is included in Appendix E.

2.4 CONSTRUCTION RECORDS

No construction records were found during this investigation.

2.5 OPERATION RECORDS

No operation records were found during this investigation.

2.6 EVAULATION OF DATA

Engineering data was obtained entirely from files of the New York State Department of Environmental Conservation. The available data, while very limited, is considered adequate and reliable for Phase I Inspection purposes, with the exception that foundation conditions and details of the upstream face of the dam are not well-known.

¹Looking downstream.

SECTION 3: VISUAL INSPECTION

3.1 FINDINGS

- a. General - The inspection was performed on 8 March 1981. The weather was cloudy with temperatures in the low 30's. The reservoir surface was at the spillway crest.
- b. Spillway - The principal spillway begins 20 feet from the left abutment. The spillway is a concrete broad-crested weir with a freeboard of 10.1 feet. The concrete on the spillway is spalled and generally deteriorated, and the construction joints are badly eroded.
- c. Auxiliary Spillway - On the right side of the dam are two stepped-weir auxiliary spillways with a crest length of 10.1 feet and 7.2 feet. Both are broad-crested weirs with a freeboard of 2.5 feet. Trees and brush are growing in the discharge channel below the auxiliary spillway.
- d. Dam - The dam is a concrete gravity structure 294 feet long with a height of 42.2 feet and a crest width of 2.5 feet. The concrete is spalled and deteriorated over the entire surface. The construction joints in the principal spillway are badly eroded with the copper seal visible in several areas. There are cracks in the downstream face of the auxiliary spillway and minor seeps are present (Photo 5, Appendix A). The wing wall along the right abutment downstream from the dam has seepage (5 to 10 gpm) at the soil-concrete contact along most of its length (Photo 6, Appendix A). There are three depressions, one at the upstream face of the dam and two behind the right wing wall that are possibly associated with the seepage under the right wing wall. The left wingwall has some seepage at its junction with the main portion of the dam. Some brush is growing in the joint between the upper and lower sections of the dam.

The rock-concrete interface at the toe of the dam is eroded in several areas (Photo 4, Appendix A). The rock is hard and appears tight, however, due to water over the spillway, it was not possible to see if any seepage was flowing beneath the dam.

- e. Outlet Works - Two 6-foot diameter outlet pipes are below the auxiliary spillway (Photo 7, Appendix A). Wooden gates on the upstream ends of the pipes were used to control the flow. Both gates are leaking and have water flowing over their downstream face. The left gate has four valves mounted on its downstream side (Photo 8, Appendix A) and its lift arm is missing. A 3-foot diameter outlet pipe below the right side of the spillway appears to have been plugged. A 12-inch outlet pipe below the left side of the spillway has a gate valve on the downstream end that is leaking around the valve stem. None of the outlet works are operable.
- f. Downstream Channel - The spillway discharges directly into the main channel; it is a deep rock channel with large boulders. The channel is extremely narrow from the dam to a point 1500 feet downstream where there is a sharp drop in the streambed forming a waterfall.

A home and a highway bridge are located 1500 feet downstream from the dam; several additional homes are located 1 mile downstream in Napanoch, New York.
- g. Reservoir - The slopes of the reservoir are moderate to steep with woods and good cover. There were no signs of instability, and sedimentation did not appear to be a problem.

3.2 EVALUATION

Visual inspection revealed several deficiencies in the structure. The following items were noted:

- 1. The right wing wall has seepage at the soil-concrete contact along most of its length;
- 2. The wooden gates on the 6-foot diameter outlet pipes have water running down their face.
- 3. The mechanical equipment for the lift gates is inoperative.
- 4. The lift arm for the left gate on the 6-foot diameter outlet pipe is missing.
- 5. The left wingwall has seepage at the junction with the main structure of the dam.

6. There is seepage through the dam on the downstream face below the auxiliary spillways.
7. The junction of the concrete and rock at the toe of the dam is eroded.
8. The construction joints in the dam are badly eroded,,
9. The entire concrete surface of the dam is spalled and deteriorated.
10. The valve on the 12-inch outlet pipe is leaking around the valve stem.
11. Brush is growing in the joint between the upper and lower sections of the dam.
12. Trees and brush are growing in the discharge channel below the auxiliary spillway.
13. Brush and trees are growing at the toe of the dam on the right abutment.

SECTION 4: OPERATION AND MAINTENANCE PROCEDURES

4.1 PROCEDURES

There are no formal operating procedures. The operation of the dam is an automatic function controlled by the crest of the spillway.

4.2 MAINTENANCE OF THE DAM

Maintenance of the dam is considered to be poor. The dam is not visually inspected and no maintenance has been performed for many years.

4.3 WARNING SYSTEM

There is no formal warning system or emergency action plan in effect.

4.4 EVALUATION

Maintenance and operating procedures for Honk Falls Dam are considered to be inadequate.

It is recommended that a maintenance program be implemented, and that formal records of examinations and necessary maintenance be recorded for future reference. A warning system and emergency action plan should be developed and put into operation. A staff gage should be installed to monitor reservoir levels above normal pool.

SECTION 5: HYDRAULIC/HYDROLOGIC

5.1 DRAINAGE AREA CHARACTERISTICS

The drainage area for Honk Falls Dam is 104.09 square miles. Included in this drainage area is Merriman Dam (Fed. I.D. No. NY 74) which has a drainage area of 95 sq. mi. The delineation of that portion of the watershed below Merriman Dam was made using the USGS quadrangle for Rondout Reservoir, New York. The drainage basin between Merriman Dam and Honk Falls Dam consists of moderate to steep slopes which are well-covered with forests and ground vegetation. Some upland storage exists in the form of flat and swampy areas.

5.2 ANALYSIS CRITERIA

The hydraulic capacity of the dam, reservoir, and spillway was assessed by utilizing the U.S. Army Corps of Engineers' Flood Hydrograph Package, HED-1 DB (Reference 11, Appendix D). The hydrologic characteristics of the watershed below Merriman Dam, specifically the Snyder's unit hydrograph parameters, were average values obtained from Hydrologic Flood Routing Model for Lower Hudson River Basin (Reference 14, Appendix D). Rainfall losses were estimated at an initial loss of 1.0 inch and a constant loss of 0.1 inch per hour thereafter.

The outflow hydrograph for Merriman Dam was developed using material presented in the Phase I Inspection Report prepared for Merriman Dam by Justin and Courtney, Inc. (see Appendix F). The outflow hydrograph for Merriman Dam was routed to Honk Lake. The hydrograph for the drainage area between Merriman Dam and Honk Falls Dam was developed and combined with the hydrograph from Merriman Dam. The resulting hydrograph was then routed through Honk Falls Dam. The Probable Maximum Flood (PMF) and 1/2 Probable Maximum Flood (1/2 PMF) were developed and routed through the reservoir.

5.3 SPILLWAY CAPACITY

With the reservoir level at the minimum top of dam, the combined capacity of the service and auxiliary spillways were determined to be 20,122 c.f.s.

5.4 RESERVOIR CAPACITY

The storage capacity of Honk Falls Dam at normal pool is 860 acre-feet. The storage capacity of the reservoir

at the minimum top of dam is 1504 acre-feet. Therefore, flood control storage of the reservoir between the spillway crest and minimum top of dam is 644 acre-feet. This volume represents a total of 0.12 inch of runoff from the watershed.

5.5 FLOOD OF RECORD

No information concerning the effects of significant floods on the dam is available.

5.6 OVERTOPPING POTENTIAL

The maximum combined capacity of the spillways is 20,122 c.f.s. to the minimum top of dam. The peak outflows of the PMF and 1/2-PMF are 92,425 c.f.s. and 42,711 c.f.s., respectively. Therefore, the spillways are capable of passing 26 percent of the PMF before overtopping would occur.

Analyses of the dam and spillway show that the dam will be overtopped during the 1/2-PMF by a maximum depth of 5.11 feet for a total duration of 12.0 hours. The PMF results in overtopping by a maximum depth of 10.61 feet for a total duration of 18.0 hours.

5.7 RESERVOIR EMPYTING POTENTIAL

The reservoir has no operable outlet pipes to drawdown the reservoir.

5.8 EVALUATION

It was determined that the spillway is capable of passing 26 percent of the PMF before overtopping the dam. Structural stability analyses based on available information indicate that factors of safety against overturning and sliding are less than the recommended guidelines for all conditions overtopping the dam. The spillway is, therefore, judged to be "seriously inadequate".

Conclusions pertain to present conditions and the effect of future development on the hydrology has not been considered.

SECTION 6: STRUCTURE STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observations - A number of significant deficiencies related to the stability of the structure were noted during the visual inspection. These include:
 1. The face of the main spillway is spalled and badly deteriorated. The copper seals in the construction joints are visible on the spillway crest, and the joints are eroded on the downstream face of the spillway.
 2. The downstream toe is eroded with exposed rebar on both ends of the main spillway. It is unknown if water is flowing along the rock concrete contact under the dam because water was flowing over the spillway at the time of inspection.
 3. While there are erosion channels and depressions in the exposed bedrock downstream of the dam, the bedrock appears tight.
 4. The downstream face of the auxiliary spillways is cracked, and minor seepage is occurring.
 5. The right wingwall next to the auxiliary spillway is cracked and has seepage at the soil-wall contact point. There are three depressions behind this wingwall which appear to be a result of this seepage.
 6. Water is leaking around the wooden gates for the two 6-foot diameter pipes below the auxiliary spillway.
- b. Design and Construction Data - No design information was available regarding the stability of the structure.
- c. Operating Records - Operating records are not available.
- d. Post Construction Changes - There were no known changes made in the dam, except that it is no longer used to provide power.

6.2 STRUCTURAL STABILITY ANALYSIS

The results of a previous stability analysis, if any, were not available for reference during this evaluation. A structural stability analysis has been conducted for the maximum section of the main spillway. The cases analyzed and respective results are as follows:

<u>Case</u>	<u>Description of Loading Conditions</u>
1	Normal operating conditions with reservoir at the spillway crest, full uplift and no tailwater.
2	Same as Case 1 with the addition of ice loading of 5000 pounds per lineal foot.
3	Reservoir level during 1/2-PMF (elev. 584.2 M.S.L.), with full uplift, and a tailwater of 9.1 feet.
4	Reservoir level during the PMF (elev. 589.7 M.S.L.), with full uplift, and a tailwater of 12.1 feet.

<u>Case</u>	<u>Factor of Safety</u>		<u>Location of Resultant</u>
	<u>Overturning</u>	<u>Sliding</u>	<u>From Toe (ft.)</u>
1	1.54	2.69	5.89
2	1.24	2.33	3.25
3	0.85	1.40	-3.79
4	0.64	0.97	-14.86

Notes: Location of middle 1/3 is 7.3 to 14.7 feet from downstream toe.

A negative sign above indicates that the resultant falls downstream of the toe.

In all cases analyzed, the factors of safety against overturning are low and the locations of the resultants fall outside of the middle 1/3. Therefore, the dam is not considered safe against overturning. In addition, the factor of safety against sliding was low for all cases. However, the structure has withstood normal loading conditions in the past without apparent structural damage and the analyses may not indicate the true field conditions or proper loading condition. Therefore, it is recommended that an in-depth engineering study of the structure be conducted to determine actual stability conditons prior to initiating any remedial measures.

6.3 SEISMIC STABILITY

The dam is located in Seismic Zone 1 which presents no hazard from earthquakes, according to the Recommended Guidelines for Safety Inspection of Dams. This determination is contingent on the requirement that static stability conditions are satisfactory and conventional safety margins exist.

SECTION 7: ASSESSMENT/RECOMMENDATIONS

7.1 ASSESSMENT

- a. Safety - The Phase I Inspection of Honk Falls Dam revealed that the spillway is "seriously inadequate," based on the Corps of Engineers screening criteria: outflows from any storm in excess of 26 percent of the PMF will overtop the dam. For this reason, the dam has been assessed as unsafe, non-emergency.

The classification of "unsafe" means that, based on an initial screening and preliminary computations, there appears to be a serious deficiency in spillway capacity, so that if a severe storm were to occur, overtopping and failure of the dam would take place, significantly increasing the hazard to loss of life downstream.

Structural stability analyses based on available information indicate that factors of safety against overturning and sliding are low for all conditions analyzed. When the dam is subjected to severe loading conditions such as ice loading or water levels overtopping the dam, the factors of safety are below recommended levels.

- b. Adequacy of Information - The information available and the observations and measurements made during the visual inspection are considered sufficient for this Phase I Inspection Report.
- c. Need for Additional Investigation - Detailed hydrologic and hydraulic investigations of the structure are considered necessary to more accurately determine the overtopping potential of the dam and to determine appropriate mitigating measures in response to the spillway inadequacy. The reservoir should be drawn down to allow for a visual inspection of the upstream face of the dam and to check for seepage under the dam without water flowing over the spillway. Investigate the areas of seepage and determine their effect on the structural stability of the dam. A detailed stability analysis of the dam is considered necessary to determine actual stability conditions.
- d. Urgency - The detailed hydrologic and hydraulic investigations and stability analysis must be initiated within three months of notification to the owner. Within one year, remedial measures

resulting from these investigations must be initiated, with completion of these measures during the following year. In the interim, a detailed emergency action plan must be developed and implemented during periods of unusually heavy precipitation. Also, around-the-clock surveillance must be provided during these periods.

7.2 RECOMMENDED MEASURES

The following remedial measures must be completed within one year:

1. The gates on the outlet pipes should be repaired, and their controls should be made operable.
2. Determine the source of and repair the area of seepage at the soil-concrete contact along the right wing wall.
3. Determine the source of and repair the area of seepage at the left wingwall.
4. Determine the cause of and repair the seepage below the auxiliary spillways.
5. Repair the eroded concrete at the toe of the dam and at the construction joints.
6. Repair all areas on the dam where the concrete is spalled and deteriorated.
7. Remove all brush and trees growing near the right abutment and on the dam.
8. Remove the trees and debris from the channel below the auxiliary spillways.
9. A program of periodic inspections and maintenance of the dam should be established. All inspections and maintenance should be recorded for future reference.
10. A staff gage should be installed to monitor reservoir levels above normal pool.

APPENDIX A
PHOTOGRAPHS

CONTENTS

- Photo 1: Upstream Side of Dam
- Photo 2: Downstream Face of Dam
- Photo 3: Gate Works
- Photo 4: Erosion at Toe on Left Abutment Showing Exposed Reinforcing Bars
- Photo 5: Auxiliary Spillway and Wingwalls From Downstream Side
- Photo 6: Seepage Along Right Wall
- Photo 7: 6-Foot Diameter Outlet Pipes
- Photo 8: Wooden Gate for Outlet Pipes

Note: Photographs were taken on 8 March 1981.

HONK FALLS DAM



Photo 1. Upstream Side of Dam
8 March 1981



Photo 2. Downstream Face of Dam
8 March 1981

HONK FALLS DAM



Photo 3. Gate Works
8 March 1981



Photo 4. Erosion at Toe on Left Abutment
Showing Exposed Reinforcing Bars
8 March 1981

HONK FALLS DAM




Photo 5. Auxiliary Spillway and Wingwalls
from Downstream Side
8 March 1981



Photo 6. Seepage Along Right Wall
8 March 1981

HONK FALLS DAM



Photo 7. 6-Foot Diameter Outlet Pipes
8 March 1981



Photo 8. Wooden Gate for Outlet Pipe
8 March 1981

APPENDIX B

VISUAL INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST

1) Basic Data

a. General

Name of Dam Honk Falls Dam

Fed. I.D. # NY 73 DEC Dam No. 177C-735

River Basin Lower Hudson River

Location: Town Napanoch County Ulster

Stream Name Rondout Creek

Tributary of Hudson River

Latitude (N) 41° 45.0' Longitude (W) 74° 22.9'

Type of Dam Concrete Gravity Dam

Hazard Category High

Date(s) of Inspection 8 March 1981

Weather Conditions Cloudy, Low 30's

Reservoir Level at Time of Inspection 569.0 ft.

b. Inspection Personnel Terry S. Hawk, Gary W. Todd, Larry A. Diday

c. Persons Contacted (Including Address & Phone No.) 914-647-8500

Albert I. Lonstein

Route 209

Terrace Hill

Ellenville, NY 12428

d. History:

Date Constructed About 1897-8 Date(s) Reconstructed _____

Designer Unknown

Constructed By Unknown

Owner Recycled Paper Corporation

2) Embankment - Not Applicable

a. Characteristics

- (1) Embankment Material _____

- (2) Cutoff Type _____

- (3) Impervious Core _____

- (4) Internal Drainage System _____

- (5) Miscellaneous _____

b. Crest

- (1) Vertical Alignment _____

- (2) Horizontal Alignment _____

- (3) Surface Cracks _____

- (4) Miscellaneous _____

c. Upstream Slope

- (1) Slope (Estimate) (V:H) _____

- (2) Undesirable Growth or Debris, Animal Burrows _____

(3) Sloughing, Subsidence, or Depressions _____

(4) Slope Protection _____

(5) Surface Cracks or Movement at Toe _____

d. Downstream Slope

(1) Slope (Estimate - V:H) _____

(2) Undesirable Growth or Debris, Animal Burrows _____

(3) Sloughing, Subsidence or Depressions _____

(4) Surface Cracks or Movement at Toe _____

(5) Seepage _____

(6) External Drainage System (Ditches, Trenches, Blanket) _____

(7) Condition Around Outlet Structure _____

(8) Seepage Beyond Toe _____

e. Abutments - Embankment Contact _____

(1) Erosion at Contact _____

(2) Seepage Along Contact _____

3) Drainage System

a. Description of System None observed

b. Condition of System _____

c. Discharge from Drainage System _____

4) Instrumentation (Monumentation/Surveys, Observation Wells, Weirs, Piezometers, Etc.) _____

None

5) Reservoir

a. Slopes Moderate, to steep wooded slopes.

b. Sedimentation None observed

c. Unusual Conditions Which Affect Dam Merriman Dam is 5 mi. upstream.

6) Area Downstream of Dam

a. Downstream Hazard (No. of Homes, Highways, etc.) 1,500 ft. below the dam is a waterfall, a house, and a highway bridge. There are also several homes in Napanoch approximately 1 mile downstream.

b. Seepage, Unusual Growth None observed at the time of inspection.

c. Evidence of Movement Beyond Toe of Dam None observed at the time of inspection.

d. Condition of Downstream Channel Narrow rock channel with large boulders.

7) Spillway(s) (Including Discharge Conveyance Channel)

Overall condition is poor.

- a. General The spillway is 184.5 ft. long with 2 auxiliary spillways
at the right side of the dam.
- b. Condition of Service Spillway The concrete spillway is spalled and deteri-
orated. The construction joints are badly eroded.
- c. Condition of Auxiliary Spillway The 2 stepped auxiliary spillways are in
fair condition with minor spalling on the concrete surfaces.
- d. Condition of Discharge Conveyance Channel Discharges into main channel.
Trees and brush are growing in the discharge channel below the auxiliary
spillway.

8) Reservoir Drain/Outlet

Type: Pipe 2 Conduit 2 Other _____

Material: Concrete _____ Metal X Other _____

Size: 2 6-ft. diameter, 1 3-ft. Length 6-ft. diameter - 17 ft. long
diameter and 1 12-in. diameter 3-ft. & 12-in. diameter-length
unknown

Invert Elevations: Entrance unknown
6 ft. - 553.6 ft.
Exit 3 ft. - 540.9 ft.
12 in. - 538.9 ft.

Physical Condition (Describe): Unobservable

Material: Iron

Joints: Good Alignment Good

Structural Integrity: 6 ft. pipes are rusted with some sedimentation in pipe.

Hydraulic Capability: _____

Means of Control: Gate X Valve _____ Uncontrolled _____

Operation: Operable _____ Inoperable X Other _____

Present Condition (Describe): 6 ft. pipes have wooden gates with water running down face. Left gate has 4 pipes with valves set in gate. Left gate lift arm is missing. 3 ft. pipe is plugged. The 12-inch pipe has a gate valve with the stem leaking.

9) Structural

- a. Concrete Surfaces The concrete is spalled, deteriorated, with eroded construction joints. Some areas are cracked with seeps; rock interfaces are being undercut by erosion.
- b. Structural Cracking The spillway of gate section and wingwalls are cracking.
- c. Movement - Horizontal & Vertical Alignment (Settlement) No signs of movement of main structure were observed.
- d. Junctions with Abutments or Embankments Rock concrete interfaces have been eroded. Right upstream abutment has some erosion with soil contact, riprap area on right abutment upstream has large depression, also undercut near wingwall. Downstream riprap is broken up. Two depressions near
(Continued next page)

right abutment, one in riprap where rock has settled, one small depression
behind wall possibly as a result of the seep under the wall.

- e. Drains - Foundation, Joint, Face None observed at the time of inspection.
- f. Water Passages, Conduits, Sluices See drains
- g. Seepage or Leakage Around wooden gates in 6 ft. pipes. Right wall has
seepage existing from soil-concrete contact along most of length. Seepage
under right wall is estimated at 5 to 10 GPM and appears clear, some pene-
tration less than 2 ft. under wall with possible piping. Spillway face
above 6 ft. discharge pipes is seeping. Left wingwall has some seepage
near joint with main structure.
- h. Joints - Construction, etc. Joints badly eroded along spillway face,
copper seal visible in several places. Some brush growing in joint between
upper and lower sections.
- i. Foundation Some water is flowing along rock fissures. Rock concrete inter-
face is eroded away in several areas. Rock is hard and appears tight, how-
ever, due to water over spillway, can not see if any seepage exists between
rock and concrete or within rock itself.
- j. Abutments See above
- k. Control Gates Wood with water flowing down face.

1. Approach & Outlet Channels Approach channel unobservable. Outlet channel contains old broken concrete channel. Water has eroded an outlet in rock beyond wingwalls. The channel has trees and brush growing in it.
- m. Energy Dissipators (Plunge Pool, etc.) None man-made. Erosion has created some pools.
- n. Intake Structures _____
- o. Stability Structure does not appear to have moved.
- p. Miscellaneous Entire structure appears in poor condition, only real exit for water is over spillway causing dam to have a full lake.

10) Appurtenant Structures (Power House, Lock, Gatehouse, Other)

- a. Description and Condition _____
- Gate works are rusted and in poor condition.
- Lift arm on left gate is missing.

APPENDIX C

HYDROLOGIC/HYDRAULIC

ENGINEERING DATA AND COMPUTATIONS

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM S.O. No. _____
APPENDIX C Sheet No. _____ of _____
HYDROLOGIC / HYDRAULIC CALC. Drawing No. _____
Computed by GWJ Checked by _____ Date _____

<u>SUBJECT</u>	<u>PAGE</u>
CHECK LIST FOR DAMS	1
HYDRAULIC AND HYDROLOGIC DATA	5
TOP OF DAM PROFILE	8
TYPICAL CROSS SECTION	9
SPILLWAY RATING	10
AUXILIARY SPILLWAY RATING	12
COMBINED SPILLWAY RATING	14
SPILLWAY CAPACITY ANALYSIS	15
HEC-1 COMPUTER ANALYSIS	17

CHECK LIST FOR DAMS
HYDROLOGIC AND HYDRAULIC
ENGINEERING DATA

AREA-CAPACITY DATA:

	<u>Elevation</u> (ft.)	<u>Surface Area</u> (acres)	<u>Storage Capacity</u> (acre-ft.)
1) Top of Dam	<u>579.1</u>	<u>86.2</u>	<u>1,504</u>
2) Design High Water (Max. Design Pool)	<u>--</u>	<u>--</u>	<u>--</u>
3) Auxiliary Spillway Crest	<u>576.6</u>	<u>75.8</u>	<u>1,345</u>
4) Pool Level with Flashboards	<u>--</u>	<u>--</u>	<u>--</u>
5) Service Spillway Crest	<u>569.0</u>	<u>44.1</u>	<u>860</u>

DISCHARGES

	<u>Volume</u> (cfs)
1) Average Daily	<u>25</u>
2) Spillway @ Maximum High Water - Top of Dam -	<u>19,876</u>
3) Spillway @ Design High Water	<u>--</u>
4) Spillway @ Auxiliary Spillway Crest Elevation	<u>12,895</u>
5) Low Level Outlet	<u>--</u>
6) Total (of all facilities) @ Maximum High Water	<u>20,122</u>
7) Maximum Known Flood	<u>Unknown</u>
8) At Time of Inspection	<u>25</u>

CREST:

ELEVATION: 579.1 ft.

Type: Concrete

Width: 2.5 ft. Length: 294 ft.

Spillover Broad-crested weir

Location Center of dam

SPILLWAY:

SERVICE

AUXILIARY

569.0 ft.

Elevation

576.6 ft.

Broad-crested weir

Type

Broad-crested weir

3.6 ft.

Width

0.8 ft.

Type of Control

X

Uncontrolled

X

Controlled:

--

Type

--

(Flashboards; gate)

--

Number

--

--

Size/Length

--

Invert Material

Anticipated Length
of Operating Service

Chute Length

20 ft.

Height Between Spillway Crest
& Approach Channel Invert
(Weir Flow)

27.6 ft.

HYDROMETEROLOGICAL GAGES:

Type: None

Location: _____

Records:

Date: _____

Max. Reading: _____

FLOOD WATER CONTROL SYSTEM:

Warning System: None

Method of Controlled Releases (mechanisms):

None

DRAINAGE AREA: 104.09 sq. mi.

DRAINAGE BASIN RUNOFF CHARACTERISTICS:

Land Use - Type: Wooded

Terrain - Relief: Varies from flat to steep

Surface - Soil: Well-drained

Runoff Potential (existing or planned extensive alterations to existing surface or subsurface conditions)

There were no known plans for altering the existing runoff patterns
at the time of inspection.

Potential Sedimentation problem areas (natural or man-made; present or future)

None observed. All slopes well-vegetated.

Potential Backwater problem areas for levels at maximum storage capacity including surcharge storage:

None observed at the time of inspection.

Dikes - Floodwalls (overflow & non-overflow) - Low reaches along the Reservoir perimeter:

Location: None

Elevation: _____

Reservoir:

Length @ Maximum Pool 2,500 ft.

Length of Shoreline (@ Spillway Crest) 7,200 ft.

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject NEW YORK DAMS
HONK FALLS DAM
RAINFALL DATA

S.O. No. _____
Sheet No. 5 of 25
Drawing No. _____
Computed by WLS Checked by GWT Date 2/20/81

RAINFALL DATA

From HAIR-33 —

DAWD AND DRAINAGE AREA ARE IN ZONE 1

$$PMF (24 HR) 200 mi^2 = 21.3 in.$$

$$DRAINAGE AREA = 9.088 sq. mi.$$

$$PMF (6-HR) = 111\% \quad PMF (24-HR) 200 mi^2$$

$$" (12-HR) = 123\% \quad " \quad " \quad "$$

$$" (24-HR) = 133\% \quad " \quad " \quad "$$

$$" (48-HR) = 142\% \quad " \quad " \quad "$$

From TP-40

$$100-HR, 24 HR RAINFALL = 7.8 in.$$

$$" \quad " \quad 12 HR \quad " \quad = 6.5 in.$$

$$" \quad " \quad 6 HR \quad " \quad = 5.3 in.$$

$$\text{Drainage Area above Roundout Reservoir} = 95 \text{ sq. mi.}$$

$$\text{Total D.A. above Honk Falls} = 104.09 \text{ sq. mi.}$$

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject THE HONK FALLS DAM
HONK FALLS DAM

Computed by WLS

Checked by GWT

S.O. No. _____

Sheet No. 6 of 25

Drawing No. _____

Date 2-15-51

HYDROLOGIC AND HYDRAULIC DATA

DRAINAGE AREA ABOVE HONK FALLS DAM NOT
CONTROLLED BY RONDOUT RESERVOIR DAM
= 63.34 SQ. MI. (MEASURED ON RONDOUT RESER-
VOIR, N.Y. GUND = 9.088 SQ. MI.

$$L_{CA} = 17,200 \text{ FT} = 3.26 \text{ MI}$$

$$L = 48,600 \text{ FT} = 9.20 \text{ MI}$$

$$T_p = C_T (L \times L_{CA})^{.3} \quad C_p = 0.63 \\ = 2.0 (9.2 \times 3.26)^{.3} \quad C_T = 2.0 \\ T_p = 5.55$$

STORAGE COMPUTATIONS

SURFACE AREA VS. ELEVATION MEASUREMENTS (TAKEN FROM GUND)

ELEV. (FT.)	AREA (ACRES)
569	44.1
580	90.0
600	172.0

→ NORMAL POOL AS SHOWN ON GUND

DEPTH = 20 FT.

AT ELEV. 549 FT. AREA = 41.9 AC. ASSUMING 1:1 S/S

$$C_p = 0.63, C_T = 2.0$$

$$T_p = C_T (L \times L_{CA})^{.3} \\ = 2.0 (9.2 \times 3.26)^{.3} \\ T_p = 5.55$$

ADJUSTMENT TO T_p FOR INTERVAL

$$T_k = T_p / 5.5 = 5.55 / 5.5 = 1.01 \text{ HR INTERVAL} \quad \text{USE 1 HR.}$$

$$T_{pk} = T_p + \frac{T_k - T_p}{4} \\ = 5.55 + \frac{1.01 - 1}{4}$$

$$T_{pk} = 5.55$$

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject COMPARISON OF DATA

S.O. No. _____

FROM MERRIMAN DAM

Sheet No. 7 of 25

(Roundout Reservoir)

Drawing No. _____

Computed by GWT


Checked by WDL

Date 5/1/81

	MICHAEL BAKER, JR., INC.	JUSTIN AND COURTNEY, INC. PHASE I INSPECTION REPORT, 1978
DRAINAGE AREA	95 Sq. Mi.	95 Sq. Mi.
t_p / C_p	5.16 / 0.63	5.16 / 0.63
RAINFALL	24 HR. PMP	12 Hr. PMP
PEAK OUTFLOW	84,597 C.F.S.	77,104 CFS

The hydrograph coefficients from the Merriman Dam Phase I Inspection Report were used to generate and match the outflow hydrograph from Merriman Dam for the 12 hour PMP. The 24 hour PMP values were then substituted to generate the PMF flows from Merriman Dam.

TYPICAL ROUTING CROSS SECTION
(CHANNEL FROM MERRIMAN DAM TO HONK FALLS)



MICHAEL BAKER, JR., INC.

THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM

TOP OF DAM PROFILE

S.O. No. _____

Sheet No. 8 of 25

Drawing No. _____


Computed by GWT

Checked by LAD

Date 3-11-81

TOP OF DAM PROFILE (LOOKING DOWNSTREAM)

LENGTH OF DAM - 294 FEET



MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM

TYPICAL CROSS SECTION

S.O. No. _____

Sheet No. 9 of 25


Drawing No. _____

Computed by GWT

Checked by LAD

Date 3-11-81

TYPICAL CROSS SECTION AT STATION 2+14



MICHAEL BAKER, JR., INC.

THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009Subject HONK FALLS DAMSPILLWAY RATING

S.O. No. _____

Sheet No. 10 of 25

Drawing No. _____

Computed by GWTChecked by LADDate 3/11/81WEIR FLOW /
 $Q = CLH^{3/2}$

BREADTH OF CREST = 3.6 FT.

L = 184.5 FT

H VARIES FROM 0 FT. TO
21 FT.C VARIES WITH H, Pgs. 5-40
TABLE 5-3 BRATER + KING

ELEVATION, (FT)	H, ' (FT)	L (FT)	C	Q, (CFS)
569.0	0	184.5	0	0
570.0	1.0	184.5	2.67	492.61
571.0	2.0	184.5	2.68	1398.51
572.0	3.0	184.5	2.73	2617.21
573.0	4.0	184.5	2.79	4118.01
574.0	5.0	184.5	3.07	6332.71
575.0	6.0	184.5	3.32	9002.51
576.0	7.0	184.5	3.32	11,344.41
576.6	7.6	184.5	3.32	12,833.81
577.6	8.6	184.5	3.32	15,448.41
578.6	9.6	184.5	3.32	18,219.71
579.6	10.6	184.5	3.32	21,139.41
580.0	11.0	184.5	3.32	22,347.21
582.0	13.0	184.5	3.32	28,711.11
584.0	15.0	184.5	3.32	35,585.31
586.0	17.0	184.5	3.32	42,934.61
588.0	19.0	184.5	3.32	50,729.91
590.0	21.0	184.5	3.32	58,947.21

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HOMK FALLS DAM S.O. No. _____
SPILLWAY RATING Sheet No. 11 of 25
(CONTINUED) Drawing No. _____
Computed by GWT Checked by LAD Date 3-19-81

WEIR FLOW

$$Q = CLH^{3/2}$$

BREADTH OF CREST = 3.6 FT. ✓
L = 3 FT. ✓
H VARIES

C VARIES WITH H, PG. 5-40
TABLE 5-3 BRATER + KING ✓

SPILLWAY STEP

ELEVATION (FT)	H (FT) ✓	L (FT) ✓	C ✓	Q (CFS)
573.0	0	3.0	0	0
574.0	1.0	3.0	2.67	8.0 ✓
575.0	2.0	3.0	2.68	22.7 ✓
576.0	3.0	3.0	2.73	42.6 ✓
576.6	3.6	3.0	2.79	57.2 ✓
577.6	4.6	3.0	3.07	90.9 ✓
578.6	5.6	3.0	3.32	131.9 ✓
579.6	6.6	3.0	3.32	168.9 ✓
580.0	7.0	3.0	3.32	184.5 ✓
582.0	9.0	3.0	3.32	268.9 ✓
584.0	11.0	3.0	3.32	363.4 ✓
586.0	13.0	3.0	3.32	466.8 ✓
588.0	15.0	3.0	3.32	578.6 ✓
590.0	17.0	3.0	3.32	698.1 ✓

SPILLWAY STEP

ELEVATION (FT)	H (FT) ✓	L (FT) ✓	C ✓	Q (CFS)
576.0	0	3.0	0	0
576.6	0.6	3.0	2.67	3.7 ✓
577.6	1.6	3.0	2.68	16.3 ✓
578.6	2.6	3.0	2.73	34.3 ✓
579.6	3.6	3.0	2.79	57.2 ✓
580.0	4.0	3.0	3.07	73.7 ✓
582.0	6.0	3.0	3.32	146.4 ✓
584.0	8.0	3.0	3.32	225.4 ✓
586.0	10.0	3.0	3.32	314.9 ✓
588.0	12.0	3.0	3.32	414.0 ✓
590.0	14.0	3.0	3.32	521.7 ✓

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM

S.O. No. _____

AUXILIARY SPILLWAY RATING

Sheet No. 12 of 25

Drawing No. _____

Computed by GWT Checked by LAD Date 3/11/81

WEIR FLOW

$$Q = CLH^{3/2}$$

FLOW OVER CREST
ASSUMING VERTICAL SIDES

L = 17.3 FT. TOTAL CREST
LENGTH COMBINING BOTH
EMERGENCY SPILLWAYS
H VARIES FROM 0 FT. TO
13.4 FT.

C VARIES WITH H, TABLE 5-3
BRATER + KING

RIGHT EMERGENCY SALLWAY



LEFT EMERGENCY SPILLWAY



TOTAL CREST RATING				
ELEVATION, (FT)	H, (FT)	L, (FT)	C	Q, (CFS)
576.6	0	17.3	0	0
577.6	1.0	17.3	3.14	54.3 /
578.6	2.0	17.3	3.21	161.9 /
579.6	3.0	17.3	3.32	298.4 /
580.0	3.4	17.3	3.32	360.1 /
582.0	5.4	17.3	3.32	720.7 /
584.0	7.4	17.3	3.32	1,156.2 /
586.0	9.4	17.3	3.32	1,655.3 /
588.0	11.4	17.3	3.32	2,210.8 /
590.0	13.4	17.3	3.32	2,817.4 /

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM

S.O. No. _____

AUXILIARY SPILLWAY RATING
(CONTINUED)

Sheet No. 13 of 25

Drawing No. _____

Computed by GWT

Checked by LAD

Date 3-11-81

FLOW OVER 1ST STEP

L = 2.5 FT TOTAL STEP WIDTH /
OF BOTH EMERGENCY SPILLWAYS
H VARIES FROM 0 FT. TO 12.4 FT.
C VARIES WITH H, TABLE 5-3
BRATER + KING
BREADTH OF WEIR = 2.5 FT. /

TOTAL 1 ST STEP RATING				
ELEVATION, (FT)	H, (FT) /	L (FT) ✓	C /	Q (CFS)
577.6	0	2.5	0	0
578.6	1.0	2.5	2.64	6.6 /
579.6	2.0	2.5	2.76	19.5 /
580.0	2.4	2.5	2.89	26.9 /
582.0	4.4	2.5	3.32	76.0 /
584.0	6.4	2.5	3.32	134.4 /
586.0	8.4	2.5	3.32	202.1 /
588.0	10.4	2.5	3.32	278.4 /
590.0	12.4	2.5	3.32	362.4 /

FLOW OVER 2ND STEP

L = 2.5 FT. TOTAL STEP WIDTH OF BOTH EMERGENCY SPILLWAYS
H VARIES FROM 0 FT. TO 11.4 FT.
C VARIES WITH H, TABLE 5-3 BRATER + KING
BREADTH OF WEIR = 2.5 FT.

TOTAL 2 ND STEP RATING				
ELEVATION, (FT)	H, (FT) /	L (FT) /	C /	Q (CFS)
578.6	0	2.5	0	0
579.6	1.0	2.5	2.64	6.6 /
580.0	1.4	2.5	2.68	11.1 /
582.0	3.4	2.5	3.19	50.0 /
584.0	5.4	2.5	3.32	104.2 /
586.0	7.4	2.5	3.32	167.1 /
588.0	9.4	2.5	3.32	239.2 /
590.0	11.4	2.5	3.32	319.5 /

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009


Subject HONK FALLS DAM S.O. No. _____
COMBINED SPILLWAY RATING Sheet No. 14 of 25
Drawing No. _____
Computed by GCUT Checked by LAD Date 3-19-81

COMBINED SPILLWAY RATING							
ELEVATION (FT)	SPILLWAY (CFS) /	SPILLWAY STEP (CFS) /	SPILLWAY STEP (CFS) /	AUXILIARY SPILLWAY CREST (CFS) /	AUXILIARY SPILLWAY 1ST STEP (CFS) /	AUXILIARY SPILLWAY 2ND STEP (CFS) /	TOTAL Q (CFS) /
569.0	0						0
570.0	492.6						492.6
571.0	1308.5						1398.5
572.0	2617.2						2617.2
573.0	4118.0	0					4118.0
574.0	6332.7	8.0					6340.7
575.0	9002.5	22.7					9025.2
576.0	11,344.4	42.6	0				11,387.0
576.6	12,833.8	57.2	3.7	0			12,894.7
577.4	15,448.4	90.9	16.3	54.3	0		15,609.9
578.6	18,219.7	131.9	34.3	161.9	6.6	0	18,554.4
579.6	21,139.4	168.9	57.2	298.4	19.5	6.6	21,690.0
580.0	23,347.2	184.5	73.7	360.1	26.9	11.1	23,003.5
582.0	28,711.1	260.9	146.4	720.7	76.6	50.6	29,973.7
584.0	35,585.3	363.4	225.4	1,156.2	134.4	104.2	37,568.9
586.0	42,934.6	466.8	314.9	1,655.3	202.1	167.1	45,740.8
588.0	50,729.9	578.6	414.0	2,210.8	278.4	239.2	54,450.9
590.0	58,947.2	698.1	521.7	2,817.4	362.4	319.5	63,666.3

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM S.O. No. _____
SPILLWAY CAPACITY ANALYSIS Sheet No. _____ of 25
Drawing No. _____
Computed by GWT Checked by LAD Date 4/7/81



SHEET 17 OF 25

REV DATE 05/23/01
PAGE 01 of 21

NATIONAL PROGRAM FOR INSPECTION OF NON-FLEURAL DAIS
HYDROLOGIC AND HYDRAULIC ANALYSIS OF HUNK FALLS DAM
UNIT HYDROGRAPH BY SNYDEK'S METHOD

JOB SPECIFICATION

NO	NHR	NMIN	LDAY	PER	IML	ALISC	IPUL	IPRF	ESTAT
300	0	60	0	0	0	0	0	-4	0
			JUPER	NAT	LPUL	IPALL	0	0	

UNITED STATES DEPARTMENT OF JUSTICE

```
APLAY= 1 NKIU= 3 LKTIU= 1
```

RIJS= 1.00 0.75 0.50 0.25 0.10

一、二、三、四、五、六、七、八、九、十、十一、十二、十三、十四、十五、十六、十七、十八、十九、二十、二十一、二十二、二十三、二十四、二十五、二十六、二十七、二十八、二十九、三十、三十一、三十二、三十三、三十四、三十五、三十六、三十七、三十八、三十九、四十、四十一、四十二、四十三、四十四、四十五、四十六、四十七、四十八、四十九、五十、五十一、五十二、五十三、五十四、五十五、五十六、五十七、五十八、五十九、六十、六十一、六十二、六十三、六十四、六十五、六十六、六十七、六十八、六十九、七十、七十一、七十二、七十三、七十四、七十五、七十六、七十七、七十八、七十九、八十、八十一、八十二、八十三、八十四、八十五、八十六、八十七、八十八、八十九、九十、九十一、九十二、九十三、九十四、九十五、九十六、九十七、九十八、九十九、一百。

SUB-AREA RUNOFF CUMULATIVE

WILFRED HYDROGRAPHIC RESERVOIR

[illegible]

ИЗДАТЕЛЬСТВО «НАУКА»

YEAR	INDG	TAREA	SNAP	IRSDA	TRSP	RATIO	ISNW	ISAE	LOCAL
1990	1	95.00	0.0	95.00	0.0	0.0	0	0	0

PRELIP DATA

SPFE	P45	R6	R12	R24	R48	R72	R96
21.30	21.30	85.00	98.00	105.00	115.00	0.0	0.0

These computed the program is 0.866

LIBRARY

Variable	Mean	SD	Min	Max
Age	38.5	10.2	25	55
Gender	0.5	0.5	0	1
Marital Status	0.6	0.5	0	1
Education	12.5	1.5	10	16
Income	45000	15000	20000	80000
Health	0.8	0.2	0	1
Exercise	0.3	0.5	0	1
Stress	0.7	0.4	0	1
Smoking	0.2	0.4	0	1
Alcohol	0.1	0.3	0	1
Family Size	2.5	1.0	1	5
Home Ownership	0.7	0.5	0	1
Job Satisfaction	0.6	0.5	0	1
Life Satisfaction	0.7	0.4	0	1

UNIT 11/12/13/14/15/16/17/18/19/20/21/22/23/24/25/26/27/28/29/30/31/32/33/34/35/36/37/38/39/40/41/42/43/44/45/46/47/48/49/50/51/52/53/54/55/56/57/58/59/60/61/62/63/64/65/66/67/68/69/70/71/72/73/74/75/76/77/78/79/80/81/82/83/84/85/86/87/88/89/90/91/92/93/94/95/96/97/98/99/100/101/102/103/104/105/106/107/108/109/110/111/112/113/114/115/116/117/118/119/120/121/122/123/124/125/126/127/128/129/130/131/132/133/134/135/136/137/138/139/140/141/142/143/144/145/146/147/148/149/150/151/152/153/154/155/156/157/158/159/160/161/162/163/164/165/166/167/168/169/170/171/172/173/174/175/176/177/178/179/180/181/182/183/184/185/186/187/188/189/190/191/192/193/194/195/196/197/198/199/200/201/202/203/204/205/206/207/208/209/210/211/212/213/214/215/216/217/218/219/220/221/222/223/224/225/226/227/228/229/230/231/232/233/234/235/236/237/238/239/240/241/242/243/244/245/246/247/248/249/250/251/252/253/254/255/256/257/258/259/260/261/262/263/264/265/266/267/268/269/270/271/272/273/274/275/276/277/278/279/280/281/282/283/284/285/286/287/288/289/290/291/292/293/294/295/296/297/298/299/300/301/302/303/304/305/306/307/308/309/310/311/312/313/314/315/316/317/318/319/320/321/322/323/324/325/326/327/328/329/330/331/332/333/334/335/336/337/338/339/340/341/342/343/344/345/346/347/348/349/350/351/352/353/354/355/356/357/358/359/360/361/362/363/364/365/366/367/368/369/370/371/372/373/374/375/376/377/378/379/380/381/382/383/384/385/386/387/388/389/390/391/392/393/394/395/396/397/398/399/400/401/402/403/404/405/406/407/408/409/410/411/412/413/414/415/416/417/418/419/420/421/422/423/424/425/426/427/428/429/430/431/432/433/434/435/436/437/438/439/440/441/442/443/444/445/446/447/448/449/450/451/452/453/454/455/456/457/458/459/460/461/462/463/464/465/466/467/468/469/470/471/472/473/474/475/476/477/478/479/480/481/482/483/484/485/486/487/488/489/490/491/492/493/494/495/496/497/498/499/500/501/502/503/504/505/506/507/508/509/510/511/512/513/514/515/516/517/518/519/520/521/522/523/524/525/526/527/528/529/530/531/532/533/534/535/536/537/538/539/540/541/542/543/544/545/546/547/548/549/550/551/552/553/554/555/556/557/558/559/560/561/562/563/564/565/566/567/568/569/570/571/572/573/574/575/576/577/578/579/580/581/582/583/584/585/586/587/588/589/590/591/592/593/594/595/596/597/598/599/600/601/602/603/604/605/606/607/608/609/610/611/612/613/614/615/616/617/618/619/620/621/622/623/624/625/626/627/628/629/630/631/632/633/634/635/636/637/638/639/640/641/642/643/644/645/646/647/648/649/650/651/652/653/654/655/656/657/658/659/660/661/662/663/664/665/666/667/668/669/670/671/672/673/674/675/676/677/678/679/680/681/682/683/684/685/686/687/688/689/690/691/692/693/694/695/696/697/698/699/700/701/702/703/704/705/706/707/708/709/710/711/712/713/714/715/716/717/718/719/720/721/722/723/724/725/726/727/728/729/730/731/732/733/734/735/736/737/738/739/740/741/742/743/744/745/746/747/748/749/750/751/752/753/754/755/756/757/758/759/760/761/762/763/764/765/766/767/768/769/770/771/772/773/774/775/776/777/778/779/780/781/782/783/784/785/786/787/788/789/790/791/792/793/794/795/796/797/798/799/800/801/802/803/804/805/806/807/808/809/810/811/812/813/814/815/816/817/818/819/820/821/822/823/824/825/826/827/828/829/830/831/832/833/834/835/836/837/838/839/840/841/842/843/844/845/846/847/848/849/850/851/852/853/854/855/856/857/858/859/860/861/862/863/864/865/866/867/868/869/870/871/872/873/874/875/876/877/878/879/880/881/882/883/884/885/886/887/888/889/890/891/892/893/894/895/896/897/898/899/900/901/902/903/904/905/906/907/908/909/910/911/912/913/914/915/916/917/918/919/920/921/922/923/924/925/926/927/928/929/930/931/932/933/934/935/936/937/938/939/940/941/942/943/944/945/946/947/948/949/950/951/952/953/954/955/956/957/958/959/960/961/962/963/964/965/966/967/968/969/970/971/972/973/974/975/976/977/978/979/980/981/982/983/984/985/986/987/988/989/990/991/992/993/994/995/996/997/998/999/1000/1001/1002/1003/1004/1005/1006/1007/1008/1009/1010/1011/1012/1013/1014/1015/1016/1017/1018/1019/1020/1021/1022/1023/1024/1025/1026/1027/1028/1029/1030/1031/1032/1033/1034/1035/1036/1037/1038/1039/1040/1041/1042/1043/1044/10

$\gamma_P = 5.16$ $C_P = 0.65$ $\gamma_A = 0$

RECEIVED

RFJUN = 1.00
RFJUN = 1.00

1. $\lambda = 0.04$ $\mu = 1.00$

[illegible]

DATE	DESCRIPTION	AMOUNT	BALANCE
1914	1914	124.00	124.00
1915	1915	124.00	124.00
1916	1916	124.00	124.00
1917	1917	124.00	124.00
1918	1918	124.00	124.00
1919	1919	124.00	124.00
1920	1920	124.00	124.00
1921	1921	124.00	124.00
1922	1922	124.00	124.00
1923	1923	124.00	124.00
1924	1924	124.00	124.00
1925	1925	124.00	124.00
1926	1926	124.00	124.00
1927	1927	124.00	124.00
1928	1928	124.00	124.00
1929	1929	124.00	124.00
1930	1930	124.00	124.00
1931	1931	124.00	124.00
1932	1932	124.00	124.00
1933	1933	124.00	124.00
1934	1934	124.00	124.00
1935	1935	124.00	124.00
1936	1936	124.00	124.00
1937	1937	124.00	124.00
1938	1938	124.00	124.00
1939	1939	124.00	124.00
1940	1940	124.00	124.00
1941	1941	124.00	124.00
1942	1942	124.00	124.00
1943	1943	124.00	124.00
1944	1944	124.00	124.00
1945	1945	124.00	124.00
1946	1946	124.00	124.00
1947	1947	124.00	124.00
1948	1948	124.00	124.00
1949	1949	124.00	124.00
1950	1950	124.00	124.00
1951	1951	124.00	124.00
1952	1952	124.00	124.00
1953	1953	124.00	124.00
1954	1954	124.00	124.00
1955	1955	124.00	124.00
1956	1956	124.00	124.00
1957	1957	124.00	124.00
1958	1958	124.00	124.00
1959	1959	124.00	124.00
1960	1960	124.00	124.00
1961	1961	124.00	124.00
1962	1962	124.00	124.00
1963	1963	124.00	124.00
1964	1964	124.00	124.00
1965	1965	124.00	124.00
1966	1966	124.00	124.00
1967	1967	124.00	124.00
1968	1968	124.00	124.00
1969	1969	124.00	124.00
1970	1970	124.00	124.00
1971	1971	124.00	124.00
1972	1972	124.00	124.00
1973	1973	124.00	124.00
1974	1974	124.00	124.00
1975	1975	124.00	124.00
1976	1976	124.00	124.00
1977	1977	124.00	124.00
1978	1978	124.00	124.00
1979	1979	124.00	124.00
1980	1980	124.00	124.00
1981	1981	124.00	124.00
1982	1982	124.00	124.00
1983	1983	124.00	124.00
1984	1984	124.00	124.00
1985	1985	124.00	124.00
1986	1986	124.00	124.00
1987	1987	124.00	124.00
1988	1988	124.00	124.00
1989	1989	124.00	124.00
1990	1990	124.00	124.00
1991	1991	124.00	124.00
1992	1992	124.00	124.00
1993			

• 162 •

100

504	21.21	17.48	3.72	10.73.10
	(339.11	457.11	62.113.015.00)	

大德長壽寺
佛林像

四尊像
佛林像

大德長壽寺
佛林像

四尊像
佛林像

WRITING FOR JERRIMAN D04

HYDROGRAPH 4-2311-60

[illegible]

★
★
★
★
★
★
★

ICOMP	IECON	ITAPE	JPLI	JPRI	INVAL	ISTAGE	ITAUO
1	1	1	0	0	1	0	0

Summary Data

ES	ISAME	LUPT	IPMP	LSR

U
C
C
T
T

ΔG	A4SK	X	SXA
			-H61-

0
J.0
J.0
J.0
J.0

	161731.00
	110228.00
	65915.00
	47533.00
	24197.00
	17708.20
	11993.04
	7155.00
	4630.00

[illegible]

APACITY =	7300.	154000.	164525.	175300.	186325.	197600.
-----------	-------	---------	---------	---------	---------	---------

ITEM	QTY	UNIT	PRICE	TOTAL
1.000	1.000	UNIT	850.	850.
2.000	2.000	UNIT	850.	1.700.
3.000	3.000	UNIT	850.	2.550.
4.000	4.000	UNIT	850.	3.400.
5.000	5.000	UNIT	850.	4.250.
6.000	6.000	UNIT	850.	5.100.
7.000	7.000	UNIT	850.	5.950.
8.000	8.000	UNIT	850.	6.800.
9.000	9.000	UNIT	850.	7.650.
10.000	10.000	UNIT	850.	8.500.
11.000	11.000	UNIT	850.	9.350.
12.000	12.000	UNIT	850.	10.200.
13.000	13.000	UNIT	850.	11.050.
14.000	14.000	UNIT	850.	11.900.
15.000	15.000	UNIT	850.	12.750.
16.000	16.000	UNIT	850.	13.600.
17.000	17.000	UNIT	850.	14.450.
18.000	18.000	UNIT	850.	15.300.
19.000	19.000	UNIT	850.	16.150.
20.000	20.000	UNIT	850.	17.000.
21.000	21.000	UNIT	850.	17.850.
22.000	22.000	UNIT	850.	18.700.
23.000	23.000	UNIT	850.	19.550.
24.000	24.000	UNIT	850.	20.400.
25.000	25.000	UNIT	850.	21.250.
26.000	26.000	UNIT	850.	22.100.
27.000	27.000	UNIT	850.	22.950.
28.000	28.000	UNIT	850.	23.800.
29.000	29.000	UNIT	850.	24.650.
30.000	30.000	UNIT	850.	25.500.
31.000	31.000	UNIT	850.	26.350.
32.000	32.000	UNIT	850.	27.200.
33.000	33.000	UNIT	850.	28.050.
34.000	34.000	UNIT	850.	28.900.
35.000	35.000	UNIT	850.	29.750.
36.000	36.000	UNIT	850.	30.600.
37.000	37.000	UNIT	850.	31.450.
38.000	38.000	UNIT	850.	32.300.
39.000	39.000	UNIT	850.	33.150.
40.000	40.000	UNIT	850.	34.000.
41.000	41.000	UNIT	850.	34.850.
42.000	42.000	UNIT	850.	35.700.
43.000	43.000	UNIT	850.	36.550.
44.000	44.000	UNIT	850.	37.400.
45.000	45.000	UNIT	850.	38.250.
46.000	46.000	UNIT	850.	39.100.
47.000	47.000	UNIT	850.	39.950.
48.000	48.000	UNIT	850.	40.800.
49.000	49.000	UNIT	850.	41.650.
50.000	50.000	UNIT	850.	42.500.
51.000	51.000	UNIT	850.	43.350.
52.000	52.000	UNIT	850.	44.200.
53.000	53.000	UNIT	850.	45.050.
54.000	54.000	UNIT	850.	45.900.
55.000	55.000	UNIT	850.	46.750.
56.000	56.000	UNIT	850.	47.600.
57.000	57.000	UNIT	850.	48.450.
58.000	58.000	UNIT	850.	49.300.
59.000	59.000	UNIT	850.	50.150.
60.000	60.000	UNIT	850.	51.000.
61.000	61.000	UNIT	850.	51.850.
62.000	62.000	UNIT	850.	52.700.
63.000	63.000	UNIT	850.	53.550.
64.000	64.000	UNIT	850.	54.400.
65.000	65.000	UNIT	850.	55.250.
66.000	66.000	UNIT	850.	56.100.
67.000	67.000	UNIT	850.	56.950.
68.000	68.000	UNIT	850.	57.800.
69.000	69.000	UNIT	850.	58.650.

CRCL	SPWID	CLQW	EXPR	ELEV	CUQL	CAREA	LXPL
1	1	1	1	1	1	1	1

340.0	600.0	3.4	1.2	0.0	0.0
340.0	600.0	3.4	1.2	0.0	0.0

DATA DATA

FILE NO	CDX	PCD	TRAIL
114440	CDX	PCD	TRAIL

860.0	3.0	1.0	2500.
-------	-----	-----	-------

CREST LENGTH U. 2500.

42734 10 14

[illegible]

4130-4111F 47-30 HOURS

PEAK (UTM) 12 3884. VI TIME 17.00 HOURS

PEAK DIFFERENCE IS 1766. AT 1146 49.00 HOURS

PEAK CUFLOW IS 5367. AT TIME 49.20 HOURS

[illegible]

佛
陀
之
聖
德

11/11/11 11:11 AM

THE UNIVERSITY OF CHICAGO

157A. [C. A.] [L. J. R.] [P. A.] [J. L.] [J. L.] [J. L.] [J. L.]

SHEET 19 OF 29

TIME	TEMP	ELNVT	ELMAX	RLNTH	STL
0000	3.0400	570.0	620.0	27000.	0.0360

DOCS SOURCE ALPHANUMERICS--STA,ELEV,SIA,ELEV--LIC

CROSS SECTION COORDINATES			
0.0	629.07	160.00	00.00
450.00	130.00	680.00	00.00
		<u>600.00</u>	850.00
			<u>00.00</u>
			580.00

556.00	2,10.00	600.00	650.00	650.00
--------	---------	--------	--------	--------

3.0 10.35 163.64 339.92

CONCLUSIONS

0.00 4020.20 8250.00 9007.14
6.136.00 64200.24 82024.31

...	622.63	515.26	577.89
-----	--------	--------	--------

590.11 590.94 601.58 604.21

0.0	40.20	1536.83	3500.08
-----	-------	---------	---------

56130.94 69260.64 82024.51

501.7

STATE IS 547.2

[illegible][illegible][illegible]

SUB-AREA MUN

KUNIFF HYDROGRAPH IC MONK LAKE

ISTAD ICDAP IELON

1

[illegible]

Time	Temperature	Pressure	Flow rate
10.0	100.0	1.0	1.0
10.5	100.0	1.0	1.0
11.0	100.0	1.0	1.0
11.5	100.0	1.0	1.0
12.0	100.0	1.0	1.0
12.5	100.0	1.0	1.0
13.0	100.0	1.0	1.0
13.5	100.0	1.0	1.0
14.0	100.0	1.0	1.0
14.5	100.0	1.0	1.0
15.0	100.0	1.0	1.0
15.5	100.0	1.0	1.0
16.0	100.0	1.0	1.0
16.5	100.0	1.0	1.0
17.0	100.0	1.0	1.0
17.5	100.0	1.0	1.0
18.0	100.0	1.0	1.0
18.5	100.0	1.0	1.0
19.0	100.0	1.0	1.0
19.5	100.0	1.0	1.0
20.0	100.0	1.0	1.0
20.5	100.0	1.0	1.0
21.0	100.0	1.0	1.0
21.5	100.0	1.0	1.0
22.0	100.0	1.0	1.0
22.5	100.0	1.0	1.0
23.0	100.0	1.0	1.0
23.5	100.0	1.0	1.0
24.0	100.0	1.0	1.0
24.5	100.0	1.0	1.0
25.0	100.0	1.0	1.0
25.5	100.0	1.0	1.0
26.0	100.0	1.0	1.0
26.5	100.0	1.0	1.0
27.0	100.0	1.0	1.0
27.5	100.0	1.0	1.0
28.0	100.0	1.0	1.0
28.5	100.0	1.0	1.0
29.0	100.0	1.0	1.0
29.5	100.0	1.0	1.0
30.0	100.0	1.0	1.0
30.5	100.0	1.0	1.0
31.0	100.0	1.0	1.0
31.5	100.0	1.0	1.0
32.0	100.0	1.0	1.0
32.5	100.0	1.0	1.0
33.0	100.0	1.0	1.0
33.5	100.0	1.0	1.0
34.0	100.0	1.0	1.0
34.5	100.0	1.0	1.0
35.0	100.0	1.0	1.0
35.5	100.0	1.0	1.0
36.0	100.0	1.0	1.0
36.5	100.0	1.0	1.0
37.0	100.0	1.0	1.0
37.5	100.0	1.0	1.0
38.0	100.0	1.0	1.0
38.5	100.0	1.0	1.0
39.0	100.0	1.0	1.0
39.5	100.0	1.0	1.0
40.0	100.0	1.0	1.0
40.5	100.0	1.0	1.0
41.0	100.0	1.0	1.0
41.5	100.0	1.0	1.0
42.0	100.0	1.0	1.0
42.5	100.0	1.0	1.0
43.0	100.0	1.0	1.0
43.5	100.0	1.0	1.0
44.0	100.0	1.0	1.0
44.5	100.0	1.0	1.0
45.0	100.0	1.0	1.0
45.5	100.0	1.0	1.0
46.0	100.0	1.0	1.0
46.5	100.0	1.0	1.0
47.0	100.0	1.0	1.0
47.5	100.0	1.0	1.0
48.0	100.0	1.0	1.0
48.5	100.0	1.0	1.0
49.0	100.0	1.0	1.0
49.5	100.0	1.0	1.0
50.0	100.0	1.0	1.0
50.5	100.0	1.0	1.0
51.0	100.0	1.0	1.0
51.5	100.0	1.0	1.0
52.0	100.0	1.0	1.0
52.5	100.0	1.0	1.0
53.0	100.0	1.0	1.0
53.5	100.0	1.0	1.0

100

	SPE	PAS	KO	RIC
1	0.00	0.00	0.00	0.00
2	0.00	0.00	0.00	0.00
3	0.00	0.00	0.00	0.00
4	0.00	0.00	0.00	0.00
5	0.00	0.00	0.00	0.00
6	0.00	0.00	0.00	0.00
7	0.00	0.00	0.00	0.00
8	0.00	0.00	0.00	0.00
9	0.00	0.00	0.00	0.00
10	0.00	0.00	0.00	0.00
11	0.00	0.00	0.00	0.00
12	0.00	0.00	0.00	0.00
13	0.00	0.00	0.00	0.00
14	0.00	0.00	0.00	0.00
15	0.00	0.00	0.00	0.00
16	0.00	0.00	0.00	0.00
17	0.00	0.00	0.00	0.00
18	0.00	0.00	0.00	0.00
19	0.00	0.00	0.00	0.00
20	0.00	0.00	0.00	0.00
21	0.00	0.00	0.00	0.00
22	0.00	0.00	0.00	0.00
23	0.00	0.00	0.00	0.00
24	0.00	0.00	0.00	0.00
25	0.00	0.00	0.00	0.00
26	0.00	0.00	0.00	0.00
27	0.00	0.00	0.00	0.00
28	0.00	0.00	0.00	0.00
29	0.00	0.00	0.00	0.00
30	0.00	0.00	0.00	0.00
31	0.00	0.00	0.00	0.00
32	0.00	0.00	0.00	0.00
33	0.00	0.00	0.00	0.00
34	0.00	0.00	0.00	0.00
35	0.00	0.00	0.00	0.00
36	0.00	0.00	0.00	0.00
37	0.00	0.00	0.00	0.00
38	0.00	0.00	0.00	0.00
39	0.00	0.00	0.00	0.00
40	0.00	0.00	0.00	0.00
41	0.00	0.00	0.00	0.00
42	0.00	0.00	0.00	0.00
43	0.00	0.00	0.00	0.00
44	0.00	0.00	0.00	0.00
45	0.00	0.00	0.00	0.00
46	0.00	0.00	0.00	0.00
47	0.00	0.00	0.00	0.00
48	0.00	0.00	0.00	0.00
49	0.00	0.00	0.00	0.00
50	0.00	0.00	0.00	0.00
51	0.00	0.00	0.00	0.00
52	0.00	0.00	0.00	0.00
53	0.00	0.00	0.00	0.00
54	0.00	0.00	0.00	0.00
55	0.00	0.00	0.00	0.00
56	0.00	0.00	0.00	0.00
57	0.00	0.00	0.00	0.00
58	0.00	0.00	0.00	0.00
59	0.00	0.00	0.00	0.00
60	0.00	0.00	0.00	0.00
61	0.00	0.00	0.00	0.00
62	0.00	0.00	0.00	0.00
63	0.00	0.00	0.00	0.00
64	0.00	0.00	0.00	0.00
65	0.00	0.00	0.00	0.00
66	0.00	0.00	0.00	0.00
67	0.00	0.00	0.00	0.00
68	0.00	0.00	0.00	0.00
69	0.00	0.00	0.00	0.00
70	0.00	0.00	0.00	0.00
71	0.00	0.00	0.00	0.00
72	0.00	0.00	0.00	0.00
73	0.00	0.00	0.00	0.00
74	0.00	0.00	0.00	0.00
75	0.00	0.00	0.00	0.00
76	0.00	0.00	0.00	0.00
77	0.00	0.00	0.00	0.00
78	0.00	0.00	0.00	0.00
79	0.00	0.00	0.00	0.00
80	0.00	0.00	0.00	0.00
81	0.00	0.00	0.00	0.00
82	0.00	0.00	0.00	0.00
83	0.00	0.00	0.00	

COMPUTED BY THE PROGRAM IS 0.000

100

SHEET 20 OF 25

1

[illegible]

[illegible]

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC FEET PER SECOND)
 AREA IN SQUARE MILES (SQUARE MILES)

RATIOS APPLIED TO FLOWS

1.00 0.75 0.50 0.25 0.10

OPERATION STATION PLAN AREA

HYDROGRAPH AT 1 95.00 1 104925 10697 20252 11993

ROUTED TO 2 95.00 1 84557 11596 30864 17506 3106

ROUTED TO 3 95.00 1 84087 60788 30719 17377 3199

HYDROGRAPH AT 4 9.09 1 11325 8433 5062 2031 1332

2 COMBINED 5 104.09 1 53147 67835 72719 19377 3441

ROUTED TO 6 104.09 1 52910 67503 42834 19271 3419

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1										STATION 3																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							
LIFTATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																											

PLUG 1		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM	
ELEVATION		365.00		561.00		571.10	
STORAGE		460.		460.		1501.	
OUTFLOW		0.		0.		20122.	
RATIO	MAXIMUM	MAXIMUM	MAXIMUM	DURATION	TIME OF	TIME OF	
CF	RESERVOIR	DEPTH	STORAGE	COVER TOP	MAX UPTURN	FAILURE	
PHF	% S.ELEV	COVER DAM	AC-FT	THICK	HOURS	HOURS	
1.00	535.73	10.64	2632.	92913.	16.00	47.00	0.0
0.75	507.34	8.25	2361.	67503.	12.00	47.00	0.0
0.50	544.23	5.11	1995.	46314.	12.00	43.00	0.0
0.25	578.83	0.0	1480.	15271.	0.0	48.00	3.0
0.10	575.03	0.0	1128.	8414.	0.0	49.00	0.0

SHEET 25 OF 25

APPENDIX D

REFERENCES

REFERENCES

1. University of the State of New York, Geology of New York, Education Leaflet 20, 1966.
2. Broughton, John G. and others, "Geologic Map of New York - Lower Hudson Sheet," New York State Museum and Science Service, Map and Chart Series No. 15, 1970.
3. Soil Conservation Service, Soil Survey of Ulster County, New York, U.S. Department of Agriculture, June 1979.
4. Bureau of Reclamation, U.S. Dept. of the Interior, Design of Small Dams, A Water Resources Technical Publication, 1977.
5. Chow, Ven Te, Handbook of Applied Hydrology, McGraw - Hill Book Company, New York, 1964.
6. Chow, Ven Te, Open Channel Hydraulics, McGraw - Hill Book Company, New York, First Edition, 1959.
7. HMR 33, "Seasonal Variations of Probable Maximum Precipitation, East of the 105th Meridian for Areas 10 to 1000 Square Miles and Durations of 6 to 48 Hours," (1956).
8. King, Horace Williams and Brater, Ernest F., Handbook of Hydraulics, Fifth Edition, McGraw - Hill Book Company, New York, 1963.
9. Soil Conservation Service, "National Engineering Handbook - Section 4, Hydrology," U.S. Department of Agriculture, 1964.
10. Soil Conservation Service, "National Engineering Handbook - Section 5, Hydraulics," U.S. Department of Agriculture.
11. U.S. Army, Hydrological Engineering Center, "Flood Hydrograph Package (HEC-1), Dam Safety Investigations, Users Manual," Corps of Engineers, Davis, California, September 1978.
12. U.S. Army, "Inventory of United States Dams," Corps of Engineers, 9 September 1978.
13. U.S. Army, Office of the Chief of Engineers, "Appendix D, Recommended Guidelines for Safety Inspection of Dams," National Program of Inspection of Dams, Volume 1, Corps of Engineers, Washington, D.C., May 1975.

14. George, Thomas S. and Taylor, Robert S., Hydrologic Flood Routing Model For Lower Hudson River Basin, Water Resources Engineers, Inc., 8001 Forbes Place, Suite 312, Springfield, Virginia, January 1977.
15. U.S. Army, Office of the Chief of Engineers, Engineering Circular EC-1110-2-163 (Draft Engineering Manual), "Spillway and Freeboard Requirements for Dams, Appendix C, Hydrometeorological Criteria and Hyetograph Estimates," (August 1975).
16. U.S. Army, Office of the Chief of Engineers, Engineering Circular EC-1110-2-188, "Engineering and Design, National Program of Inspection of Non-Federal Dams," Corps of Engineers, Washington, D.C., 30 December 1977.
17. U.S. Army, Office of the Chief of Engineers, Engineer Technical Letter No. ETL 1110-2-234, "Engineering and Design, National Program of Inspection of Non-Federal Dams, Review of Spillway Adequacy," Corps of Engineers, Washington, D.C., 10 May 1978.
18. Terzaghi, Karl, and Peck, Ralph B., Soil Mechanics in Engineering Practice 2d., ed., John Wiley & Sons, Inc., New York, 1967.

APPENDIX E


DRAWINGS

CONTENTS


Location Plan

Watershep Map

Field Sketch






SCALE 1:24000




REFERENCES:

1. U.S.G.S. 7.5 NAPANOCH, N.Y. QUADRANGLE. 1956
2. U.S.G.S. 7.5 RONDOUT RESERVOIR, N.Y. QUADRANGLE. 1969
3. U.S.G.S. 7.5 KERHONKSON, N.Y. QUADRANGLE. 1969
4. U.S.G.S. 7.5 ELLENVILLE, N.Y. QUADRANGLE. 1969

LOCATION PLAN
HONK FALLS DAM




Scale 1:250,000



REFERENCES:
1. U.S.G.S. 1:250,000 SCRANTON, PA., N.Y., N.J.
QUADRANGLE. REVISED 1976

WATERSHED MAP
HONK FALLS DAM

~ RESERVOIR ~



HONK FALLS DAM
FIELD SKETCH

APPENDIX F
BACKGROUND DOCUMENTS

VI ap 178
Dam 735
LH

(NOTICE: After filling out one of these forms as completely as possible for each dam in your district, return it at once to the Conservation Commission, Albany.)

STATE OF NEW YORK
CONSERVATION COMMISSION
ALBANY

DAM REPORT

August 4, 1914
(Date)

CONSERVATION COMMISSION,

DIVISION OF INLAND WATERS.

GENTLEMEN:

I have the honor to make the following report in relation to the structure known as the Honk Falls Dam.


This dam is situated upon the London Creek
(Give name of stream)
in the Town of Warren, Ulster County,
about 1.5 miles from the Village or City of Nesamatche
(State distance)

The distance down stream from the dam, to the Albany London Creek
(Up or down) (Give name of nearest important stream or of a bridge)
is about 2 miles Honk Falls Power Co
(State distance)

The dam is now owned by Charles P. Dickinson
(Give name in full)
and was built in or about the year 1897, and was extensively repaired or reconstructed during the year _____.

As it now stands, the spillway portion of this dam is built of concrete
(State whether of masonry, concrete or timber)
and the other portions are built of concrete
(State whether of masonry, concrete, earth or timber with or without rock fill)

As nearly as I can learn, the character of the foundation bed under the spillway portion of the dam is rock with sandstone and under the remaining portions such foundation bed is granite.



May 13-16 - Good Condition A.R. M. This
 3" water over crest

The total length of this dam is 255 feet. The spillway or waste-weir portion, is about ²⁰⁰175 feet long, and the crest of the spillway is about 6 feet below the top of the dam.

The number, size and location of discharge pipes, waste pipes or gates which may be used for drawing off the water from behind the dam, are as follows: *one 6" waste & one 6' discharge waste pipes from west end.*

State briefly, in the space below, whether, in your judgment, this dam is in good condition, or bad condition, describing particularly any leaks or cracks which you may have observed.)

Dam is in good condition. There are numerous leaks thru the concrete, largest about an inch in diameter, but these make loss insignificant.


Reported by *Richard L. Hyatt*
(Signature)

(Address—Street and number, P. O. Box or R. P. D. route)


(Name of place)

(SEE OTHER SIDE)

(In the space below, make one sketch showing the form and dimensions of a cross section through the spillway or waste-weir of this dam, and a second sketch showing the same information for a cross section through the other portion of the dam. Show particularly the greatest height of the dam above the stream bed, its thickness at the top, and thickness at the bottom, as nearly as you can learn.)



(In the space below, make a third sketch showing the general plan of the dam, and its approximate position in relation to buildings or other conspicuous objects in the vicinity.)



State Conservation Commission

Albany N. Y.

GENTLEMEN:

Regarding our Dam at HONK FALLS near NAPANOCH N. Y.
OWNED BY C. P. DICKINSON
FITCHBURG MASS.

BUILT 1898

FOR a Hydroelectric plant

ON rock foundation


DAM and SPILLWAY, of concrete

Length of Spillway 200 ft

Total length of Dam and Spillway, 275 ft

Discharges through two 6ft Steel Penstocks 13 ft below top of Dam.

① 23
Wich



CONSERVATION COMMISSION

COMPTROLLER

APR 6 1912

RECEIVED

MERRIMAN DAM

NY 74

SECTION 3 - HYDROLOGY/HYDRAULICS

U.S. OF
HONK FALLS
DAM

The design flood used for Merriman Dam and Rondout Reservoir is the Probable Maximum Flood (PMF), according to the Recommended Guidelines for Safety Inspection of Dams. The PMF was derived from the adjusted 12 hour Probable Maximum Precipitation (PMP) and was routed through the reservoir using the U.S. Army Corps of Engineers computer program HEC-1. From this analysis, peak outflows and storages were determined for various percentages of the PMF. The routing analysis revealed that 23,645 acre-feet of water would be stored for the peak PMF outflow of 77,104 cfs. The storage input, as derived on sheet #A-16 in the appendix, shows that this storage corresponds to a reservoir elevation of 851.0, 11.0 feet above spillway crest and 9.0 feet below the top of the dam. Therefore, there is no danger of overtopping from a storm resulting in a flood equal to or less than the Probable Maximum Flood.

According to "The Delaware Water Supply News", March 1, 1940:

"The maximum flood peak of record in the Rondout is that of August, 1928, reaching 26,715 cubic feet per second, with an indicated occurrence of once in 55 years; 14,000 cubic feet per second and over had been observed to occur three times in 25 years".

If inflow to the reservoir is assumed as 2 cfs per square mile of drainage area, drawdown from spillway crest to elevation 720 would take place in approximately 69 days.

HYDROLOGIC AND HYDRAULIC CALCULATIONS

JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET NO. 1 OF

DATE 7/6/78

COMP. BY FEP

CHECKED BY DBC

NAME OF CLIENT

PROJECT MERRIMAN DAM

STAGE-DISCHARGE RELATIONSHIP

$Q = CLH^{3/2}$ (SPILLWAY CREST).

$C = 3.4$
 $L = 600'$ } $CL = 2040$

ELEVATION	HEAD	$H^{3/2}$	DISCHARGE
840.0	0	0	0
840.5	0.5	0.35	714
841.0	1.0	1.00	2040
842.0	2.0	2.83	5773
843.0	3.0	5.20	10608
844.0	4.0	8.00	16320
845.0	5.0	11.18	22807
848.0	8.0	22.63	46165
850.0	10.0	31.62	64505
{ 855.0	15.0	58.09	117109
{ 860.0	20.0	89.44	180311

$\rightarrow C = 3.2, L = 630, CL = 2016$

DETERMINE DISCHARGE THROUGH OUTLET WORKS.

(MAXIMUM DISCHARGE @ EL. 840 = 890 MILLION GALLONS/DAY
= 1377 cfs.


DISCHARGE @ EL. 720 (OVERFLOW WEIR) = 700 MILLION GALLONS/DAY
= 1083 cfs.

STRAIGHT LINE RELATIONSHIP FROM EL. 840 TO EL. 720

\rightarrow THIS INFORMATION PROVIDED BY MR. KEVIN CLOONAN
GRAHAMSVILLE, N.Y., 12740
POB 94

CHECKED BY DBc

PROJECT Merriman Dam



JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA


SHEET NO. 3 OF
DATE 7/25/78
COMP. BY FEK
CHECKED BY DBC

NAME OF CLIENT

PROJECT MERAPIHAN DAM

TOTAL DISCHARGE DETERMINATION

ELEVATION	OUTLET WORKS	SPILLWAY	TOTAL DISCHARGE
840	1377	0	1377
841	1380	2040	3420
842	1382	5773	7155
843	1385	10608	11993
844	1388	16320	17708
845	1390	22807	24197
848	1398	46165	47563
850	1410	64505	65915
855	1419	117109	118528
860	1428	180311	181739



Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET NO. 4 OF

DATE 7/6/78

COMP. BY FEF.

CHECKED BY DAC

NAME OF CLIENT.

PROJECT

MERRIMAN DAM

STAGE-STORAGE RELATIONSHIP

AREA @ 840, SPILLWAY CREST: 3.25 SQ. MI. = 2080 ACRES.

AREA @ 860, TOP OF DAM = 3.57 SQ. MI = 2285 ACRES.

$$(2285-2080)/20' = 205/20 = 10.25 \approx 10 \text{ ADZES/yr.}$$
$$AREA = 10 DEPTH + 2000$$
$$STORAGE = 50D + 2080 = 5D^2 + 2080D$$


ELEVATION DEPTH SD² 20800 STOPPER

840.0	0	0	0	0
840.5	0.5	1.25	1040.0	1041
841.0	1.0	5.0	2080.0	2085
842.0	2.0	20.0	4160.0	4180
843.0	3.0	45.0	6240.0	6285
844.0	4.0	80.0	8320.0	8400
845.0	5.0	125.0	10400.0	10525
848.0	8.0	320.0	16640.0	16960
850.0	10.0	500.0	20800.0	21300
855.0	15.0	1125.0	31200.0	32325
860.0	20.0	2000.0	41600.0	43600

SHEET NO. 5 OF _____
DATE 7/4/78
COMP. BY FBF
CHECKED BY DBC

PROJECT.

MERRIMAN DAM



JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET NO. 6 OF
DATE 7/7/78
COMP. BY FEF
CHECKED BY DBC

NAME OF CLIENT

PROJECT MERRIMAN DAM

PROBABLE MAXIMUM FLOOD COMPUTATIONS

DRAINAGE AREA = 95 sq. mi. PMP = 23"

PMP in ZONE #1 - 75% OF 10 SQ. MILES, 6 HOUR VALUES

ISOHYETAL FIT REDUCTION FACTOR = 13.0%

R. ADJUSTED PMP = $23" \times .13 = 2.99$

REDUCTION = $23 - 2.99 = 20.01$

$20.01 \times .75 = 15.01$, USE 15 INCHES.

12 HR PMP = $20.01 \times .84 = 16.8$ INCHES.

$C_T = 2.0$
 $C_p = .625$

$L = 11.80$ MILES
 $L_{CA} = 2.0$ MILES

$T_p = C_T (L \times L_{CA})^{.3}$
 $= 2.0 (11.8 \times 2.0)^{.3} = 5.16$

JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

NAME OF CLIENT NYSDEC

PROJECT Merriman Dam

SHEET NO. 7 OF

DATE 8/15/18

COMP. BY DBC

CHECKED BY RELH

$$T_R = T_P / 5.5 = .94 \approx 1.0$$

USE 12 HOUR STORM

Time (hours)	Rainfall	
	Σ	Incr
0-1	.20	.20
1-2	.40	.20
2-3	.80	.40
3-4	1.20	.40
4-5	2.25	1.05
5-6	3.45	1.20
6-7	10.80	7.35
7-8	13.20	2.40
8-9	14.70	1.50
9-10	16.20	1.50
10-11	16.50	.30
11-12	16.80	.30

use minimum loss rate of .1 inch/hour

Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET No. 8 OF

DATE 7/25/78

COMP. BY FEF

CHECKED BY DBC

NAME OF CLIENT.**PROJECT**

MERRIMAN DAM

DRAWDOWN COMPUTATIONS

DRAWDOWN TIME = 69 DAYS

$A_1 = \text{AREA AT EL. 840}$

$S_1 = \text{Storage at EL. 840} = 154000 \text{ Acre Ft.}$

$A_2 = \text{AREA AT EL. 720}$

2nd SYDRALE AT EL. 720 & 7300 ALONG RT.

D = DEPTH.

$$(A_1 + A_2)/2 \times D = S_1 - S_2$$

$$(2080 + A_2)/2 = (154000 - 7300)/0$$

$$2080 + A_2 = 2(154000 - 7300)/120$$

$$A_2 = 2445 - 2080$$

$$A_2 = 365 \text{ Acres}$$

$$R_{13\%} = (2080 - 365) / 120' = 14.3 \text{ ACRES/FR.}$$

$$A_{\text{AREA}} = 14.30 + A_2$$

$AREA = 1430 + 365$

$$STORAGE = 7.15 D^2 + 365 D$$

SEE SHEET #9

ELEVATION ⁺	DISCHARGE (CFS)	FROM/TO (ELEVATION)	INCREMENT (STORAGE)	TIME (HRS.)	TIME (DAYS)
840	1187	840/830	20095	205	8.54
820	1140	830/810	35900	381	15.88
800	1077	810/790	30180	339	14.13
780	1020	790/770	24460	290	12.08
760	987	770/760	10085	124	5.17
750	967	760/720	26040	326	13.58
720	0				

A-19

TOTAL TIME = 69 Days.

* ACCOUNTS FOR 2 cfs/SQ MI DRAINAGE AREA AS INFLOW

$$2NF_{low} = 2 \times 95 = 190 \text{ g/s}$$

JUSTIN & COURTNEY, INC.
Division of O'Brien & Gere Engineers, Inc.
PHILADELPHIA, PA

SHEET NO. 9 OF

DATE 7/25/78

COMP. BY FF

CHECKED BY DBC

NAME OF CLIENT

PROJECT MELLIAM DAM

$$STORAGE = 7.15 D^2 + 365 D$$

ELEVATION	DEPTH (Ft.)	$7.15 D^2$	$365 D$	STORAGE (Ac. Ft.)	INCREMENT STORAGE
840	120	102960	43800	146760	20095
830	110	86515	40150	126665	35900
810	90	57915	32850	90765	30180
790	70	35035	25550	60585	24460
770	50	17875	18250	36125	10085
760	40	11440	14600	26040	26040
720	0	0	0	0	

 450-1 VERSION DATED JAN 1973
 UPDATED AUG 74
 CHANGE NO. 01

HERRIMAN DAM
 PHF HYDROLOGY
 NATIONAL DAM INSPECTION PROGRAM

JOB SPECIFICATION

NQ NHR NMIN IDAY IHR IMIN METRC IPLT IPRT NSTAN
 48 1 0 1 0 0 0 0 0 0 0
 JOPER NHT
 3 0

SUN-AREA RUNOFF COMPUTATION

ISTAN ICOMP IECON ITAPE JPLT JPRT INAME
 1 0 0 0 0 0 DC

HYDROGRAPH DATA

IMYDC IJNG YAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
 0 1 95.00 0.00 0.00 0.00 0.00 0 0 0

PRECIP DATA

NP STORM DAJ NAK
 12 0.00 0.00 0.00
 PRECIP PATTERN

-20 .20 .40 .40 .40 1.05 1.20 7.35 2.40 1.50 1.50
 .30 .30

LOSS DATA

STKPS OLTR RTIOL ERAIN STKPS RTIOL STPTL C45IL ALS4X RTIMP
 0.00 0.00 1.00 0.00 0.00 1.00 0.00 .10 0.00 0.00

UNIT HYDROGRAPH DATA

TP= 5.16 CP= .63 NTA= 0

RECESSION DATA

STRTQ= 0.00 TPCEN= 0.00 RTIOP= 1.00
 APPROXIMATE CLARK COEFFICIENTS FROM GIVEN SNYDER CP AND TP ARE TC= 6.06 AND R= 4.61 INTERVALS

UNIT HYDROGRAPH 28 END-OF-PERIOD COEFFICIENTS, LAG= 5.14 HOURS, CP= .63 VOL= 1.00
 56A. 2062. 4940. 5954. 7255. 7474. 6635. 5345. 4391. 3459.
 2783. 2234. 1801. 1443. 1155. 937. 756. 606. 488. 392.
 315. 256. 206. 164. 112. 105. 36. 59.

END-OF-PERIOD FLOW

TIME	RAIN	EXCS	COMP Q
1 1 0	.20	.10	57.
1 2 0	.20	.10	261.
1 3 0	.40	.30	780.
1 4 0	.60	.30	1789.
1 5 0	1.05	.05	3615.

1	14	0	0.00	0.00	0.00	95427.
1	15	0	0.00	0.00	0.00	73766.
1	16	0	0.00	0.00	0.00	51056.
1	17	0	0.00	0.00	0.00	49545.
1	18	0	0.00	0.00	0.00	40013.
1	19	0	0.00	0.00	0.00	32188.
1	20	0	0.00	0.00	0.00	25892.
1	21	0	0.00	0.00	0.00	20827.
1	22	0	0.00	0.00	0.00	16753.
1	23	0	0.00	0.00	0.00	13476.
2	0	0	0.00	0.00	0.00	10840.
2	1	0	0.00	0.00	0.00	8720.
2	2	0	0.00	0.00	0.00	7014.
2	3	0	0.00	0.00	0.00	5842.
2	4	0	0.00	0.00	0.00	4538.
2	5	0	0.00	0.00	0.00	3645.
2	6	0	0.00	0.00	0.00	2927.
2	7	0	0.00	0.00	0.00	2338.
2	8	0	0.00	0.00	0.00	1864.
2	9	0	0.00	0.00	0.00	1447.
2	10	0	0.00	0.00	0.00	1103.
2	11	0	0.00	0.00	0.00	486.
2	12	0	0.00	0.00	0.00	264.
2	13	0	0.00	0.00	0.00	135.
2	14	0	0.00	0.00	0.00	31.
2	15	0	0.00	0.00	0.00	14.
2	16	0	0.00	0.00	0.00	0.
2	17	0	0.00	0.00	0.00	0.
2	18	0	0.00	0.00	0.00	0.
2	19	0	0.00	0.00	0.00	0.
2	20	0	0.00	0.00	0.00	0.
2	21	0	0.00	0.00	0.00	0.
2	22	0	0.00	0.00	0.00	0.
2	23	0	0.00	0.00	0.00	0.
3	0	0	0.00	0.00	0.00	0.

SUM 16.90 15.60 951479.

PEAK 100494. 6-HOUR 07684. 24-HOUR 34931. 72-HOUR 19822. TOTAL VOLUME 951478.
 CFS 100494. INCHES 8.59 15.25 15.53 15.51
 40-FT 41502. 77258. 78675. 78675.

HYDROGRAPH ROUTING
 ISTAT ICOMP ICCOH ITARE JPLY JPPY INAME
 2 1 0 0 0 0
 ROUTING DATA
 CLOSS AVG TRES ISAME
 0.0 0.00 0.00 1 0
 NSTOL LAG M4SKX X YSK STOPA
 0 0 0.00 0.00 0.000 -1.

STATS 4180. 6285. 8400. 10525. 16060. 21300. 32325. 41609.

AD-A105 797

BAKER (MICHAEL) JR INC BEAVER PA
NATIONAL DAM SAFETY PROGRAM. HONK FALLS DAM (INVENTORY NUMBER N--ETC(U)
AUG 81 6 KESTER

F/G 13/13

DACH51-81-C-0010

NL

UNCLASSIFIED

2 of 2
AD-A105 797



END
DATE
FILMED
11-81
DTIC

1	6	0	720.	5389.	1194.
1	7	0	1511.	11315.	2479.
1	8	0	3153.	23769.	5324.
1	9	0	5993.	42689.	11322.
1	10	0	9930.	64481.	22379.
1	11	0	14378.	84104.	34106.
1	12	0	19540.	96580.	54244.
1	13	0	21670.	98841.	67683.
1	14	0	23336.	91808.	75630.
1	15	0	23645.	90106.	77104.
1	16	0	22976.	67420.	73314.
1	17	0	21693.	55321.	67789.
1	18	0	20083.	44797.	50768.
1	19	0	18347.	36100.	53430.
1	20	0	16624.	29040.	46345.
1	21	0	14973.	23359.	40147.
1	22	0	13424.	18790.	34722.
1	23	0	12015.	15115.	24606.
2	0	0	10761.	12158.	25053.
2	1	0	1645.	9700.	21510.
2	2	0	8644.	7867.	18452.
2	3	0	7746.	5328.	15940.
2	4	0	6939.	5090.	13760.
2	5	0	6219.	4092.	11947.
2	6	0	5573.	3286.	10358.
2	7	0	4930.	2632.	9318.
2	8	0	4468.	2101.	7918.
2	9	0	4000.	1455.	6834.
2	10	0	3572.	1275.	6071.
2	11	0	3166.	796.	5347.
2	12	0	2783.	375.	4664.
2	13	0	2439.	197.	4052.
2	14	0	2134.	81.	3507.
2	15	0	1864.	22.	3058.
2	16	0	1628.	7.	2671.
2	17	0	1421.	0.	2332.
2	18	0	1241.	0.	2136.
2	19	0	1093.	0.	1777.
2	20	0	946.	0.	1552.
2	21	0	826.	0.	1355.
2	22	0	721.	0.	1193.
2	23	0	629.	0.	1037.
3	0	0	550.	0.	301.

SUM

94593.

SFS	PEAK	5-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
INCHES	77104.	70481.	36967.	19702.	945698.
AC-FT		6.90	14.48	15.43	15.43
		34967.	73362.	78197.	78197.

RUNOFF SUMMARY, AVERAGE FLOW

HYDROGRAPH AT ROUTED TO		PEAK	6-HOUR	24-HOUR	72-HOUR	AREA
1		100494.	87684.	30931.	19022.	95.00
2		77104.	70481.	36967.	19702.	95.00

APPENDIX G
STRUCTURAL STABILITY


MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Houk Falls DAM S.O. No. 13838-00-ALH
Typical Cross Section Sheet No. 1 of 16
Station 2+14 Drawing No. _____
Computed by DWM. Checked by SH Date May 6, 1981

Stability Analysis

$\gamma_c = 150$ PCF
Consider Sectional
Width of 1 FT



MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Honk Falls Dam
Stability Analysis

S.O. No. 13833-W-ARA

Sheet No. 2 of 16

Drawing No. _____

Computed by DWM Checked by TSH Date May 6, 1981

Section	W (lb)	Arm (FT)	Moment (K-FT)
①	4(150)(17.1)	20	205.2
②	1/2(18)(17.1)150	2/3(18)	277.02
③	22(15)150	11	544.5
$\Sigma W = 82845 \text{ lb}$			$\Sigma M = 1026.72 \text{ K-FT}$

Resultant = 82.845 K

$$\bar{X} = \frac{1026.72 \text{ K-FT}}{82.845 \text{ K}} = 12.39'$$

O.K., within Middle Third $7.33' < \bar{X} \leq 14.67'$

- Case I Normal operating Conditions with reservoir level at the spillway crest, full uplift, and no tailwater
- Case II Same as Case I with the addition of ice loading of 5,000 lb/FT OF WALK
- Case III Reservoir level during 1/2 PMF, Full uplift as in Case I, with tailwater \cong 60% full value for overflow section or full value for non-overflow section
- Case IV Reservoir level during PMF, Full uplift as in Case I, with tailwater \cong 60% full value for overflow section or full value for non-overflow section

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Houk Falls Dam
Stability Analysis

Computed by DWM

Checked by TS H


S.O. No. 13988-D)-APP

Sheet No. 3 of 16

Drawing No. _____

Date May 6, 1931

Case I (over flow Section)



$$\text{Pressure at Base of Dam} = 32.1 (62.5) = 2,006.25 \text{ lb/ft}^2 = 2.006 \text{ k/ft}^2$$

$$\text{Resultant Hydro Static Force} = \frac{1}{2} (32.1) (2.006) (1) = 32.2 \text{ Kips}$$

$$\text{Moment Arm} = \frac{1}{3} (32.1) = 10.7 \text{ Ft above base of Dam (resultant location)}$$

$$\text{Resultant Uplift Force} = \frac{1}{2} (2.006) (22) = 22.07 \text{ K}$$

$$\text{Moment Arm} = \frac{2}{3} (22) = 14.67 \text{ from Right side of Dam (resultant location)}$$

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HANK FALLS DAM
Stability Analysis

Computed by DWM

Checked by ESL

S.O. No. 13938-05-AAA

Sheet No. 4 of 16

Drawing No. _____

Date May 6, 1931

Now Consider Bearing Pressure, i.e. Reaction of Foundation

$$BP_B = \frac{\Sigma W}{T} \left(1 - \frac{e(G)}{T} \right)$$

$$BP_A = \frac{\Sigma W}{T} \left(1 + \frac{e(G)}{T} \right)$$

$$\Sigma M_C \Rightarrow r = \frac{\Sigma H (MA_H)}{\Sigma W} = \frac{32.2 (10.7)}{82.845}$$

$$r = 4.159'$$

$$(12.39 - 4.159 = 8.231') \quad e = \frac{22}{2} - 8.231 = 2.769$$

$$BP_B = \frac{82.845}{22} \left(1 - \frac{2.769(6)}{22} \right)$$

$$BP_B = .922 \text{ KSF}$$


$$BP_A = \frac{82.845}{22} \left(1 + \frac{2.769(6)}{22} \right)$$

$$BP_A = 6.609 \text{ KSF}$$

This initial Calculation Does Not Consider Uplift

$$\text{Uplift pressure at B} \rightarrow UP_B = 2.006 \text{ KSF}$$

$$UP_A = 0$$



MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009


Subject Hark Falls Dam
Stability Analysis

S.O. No. 13989-00-ARA

Sheet No. 5 of 16

Drawing No. _____

Computed by DWM Checked by ESL Date May 6, 1991



Overturning

$$F.S. = \frac{\sum MA \text{ Resisting Overturning}}{\sum MA \text{ Causing Overturning}} = \frac{82.845(12.39)}{32.2(10.7) + 22.07(14.67)}$$

$F.S._{\text{overturning}} = 1.536$

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Honk Falls Dam
Stability Analysis

S.O. No. 13333-01-ALL

Sheet No. 6 of 16

Drawing No. _____

Computed by DWM

Checked by TSU

Date May 6, 1931

Sliding

General Eq. Forces Resisting Sliding

$$R = (\sum F_{vertical}) \tan \phi + s A$$

$$\phi = 35^\circ \quad s = 2 \text{ KSF} \quad \tan 35^\circ = .700$$

$$\sum F_v = 82.845 - 22.07 = 60.775 \text{ Kips}$$

$$A = 22 (1) = 22 \text{ FT}^2$$

$$R = (60.775) .700 + 2 (22)$$

$$= 86.543 \text{ Kips.}$$

$$H = 32.2 \quad F.S. = \frac{R}{H} = \frac{86.543}{32.2}$$

$F.S. = 2.688$ <p style="text-align: center;"><small>sliding</small></p>
--

ϕ = Angle of internal Friction
of Foundation Material

$\sum F_v$ = Summation of Vertical
Forces

s = Unit Shear Strength at
zero Normal loading along
potential failure plane

A = Area of potential failure
plane developing "s"

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Honk Falls Dam
Stability Analysis

Computed by DWM Checked by TS H Date May 6, 1991


S.O. No. 13333-00-AAA

Sheet No. 7 of 16

Drawing No. _____

Date May 6, 1991

Case II (overflow Section)



I = Force Caused by expansion of solidifying ice

Overturning

$$F.S. = \frac{82.845(12.39)}{32.2(10.7) + 22.07(14.67) + 5(32.1)}$$

$$F.S. = 1.238$$

overturning

Sliding

$$H = 32.2 + 5 = 37.2$$

$$F.S. = \frac{86.543}{37.2}$$

$$F.S. = 2.326$$

overturning

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM
Stability Analysis

S.O. No. 13833-25-APP

Sheet No. 8 of 16


Drawing No. _____

Computed by DWM

Checked by BSH

Date May 5, 1931

Case III (overflow Section)



Consider a section one (1)
foot wide

$$\text{Resultant Hydro Static Force on Face} = \left[\frac{1}{2} (2.731 - .725) 32.1 + .725 (32.1) \right] (1)$$

$$= 55.469 \text{ Kips}$$

$$\text{Resultant location} = \frac{\left[\frac{1}{2} (2.731 - .725) 32.1 \right] \frac{32.1}{3} + \left[.725 (32.1) \right] \frac{32.1}{2}}{55.469}$$

$$= 12.945' \text{ above base level}$$

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Hart Falls Dam
Stability Analysis
Computed by DM

S.O. No. 12333-25-AAA
Sheet No. 9 of 16
Drawing No. _____
Date May 7, 1931

Resultant Hydrostatic Force on Downstream Face
 $= \frac{1}{2} [0.6(9.1)]^2 62.5 = 931.6 \text{ lbs} = .932 \text{ kips}$

Resultant Location = $\frac{0.6(9.1)}{3} = 1.82 \text{ FT}$ above base level

Resultant Uplift Force = $\left(\frac{0.569 + 2.731}{2} \right) 22 = 36.3 \text{ kips}$

Resultant location = $\frac{\left[\frac{1}{2} (2.731 - 0.569) 22 \right] \frac{22}{3} + \left[0.569(22) \right] \frac{22}{2}}{36.3}$

$= 8.598 \text{ FT}$ FROM upstream face

$22 - 8.598 = 13.402 \text{ FT}$ FROM DOWNSTREAM FACE

Bearing Pressure (excluding Uplift)

$\Sigma M_c \Rightarrow r$ $r = \frac{(55.467)(12.945) - (.932)(1.82)}{82.845}$

$r = 8.647'$

$12.37 - 8.647 = 3.743'$ FROM DOWNSTREAM FACE

$e = \frac{22}{2} - 3.743 = 7.257$ Not within middle third


$7.257 > 3.667$

$BP_D = \frac{82.845}{22} \left(1 - \frac{7.257(6)}{22} \right)$

$BP_D = -3.687 \text{ K}$

$BP_A = \frac{82.845}{22} \left(1 + \frac{7.257(6)}{22} \right)$

$= 11.219 \text{ K}$



MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HONK FALLS DAM
Stability Analysis

S.O. No. 13938-05-A44

Sheet No. 10 of 16

Drawing No. _____

Computed by DUM

Checked by SL


Date MAY 7, 1931

Negative Bearing Pressure (Tension) Does NOT exist

Revise Bearing Pressure Diagram

$$\frac{1}{2} [3(3.743)] BP_0 = 82.845$$


$$BP_0 = 14.756 \text{ K/ft}^2$$



14.756 KSF

(Excluding Uplift)

Resultant Loadings



MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Bull Falls Dam S.O. No. 13983-D-ARH
Stability Analysis Sheet No. 11 of 16
Drawing No. _____
Computed by DWM Checked by W. 4 Date May 7, 1991

Overturning $\Sigma M_n \Rightarrow$

$$F.S._{overturning} = \frac{(82.845)(12.39) + (16.82)(.932)}{(55.469)(12.945) + (36.3)(13.432)}$$

$$F.S._{overturning} = 0.854$$

Sliding

$$R = (F_v) \tan \phi + SA \quad R = (46.545) \cdot 7 + 2(22)$$

$$H = 55.469 - .932 = 54.537^k$$

$$F.S. = \frac{R}{H} = \frac{76.582}{54.537}$$

$$F.S._{sliding} = 1.404$$

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject HULL FALLS DAM
Stability Analysis


S.O. No. 13888-03-ADA

Sheet No. 12 of 16

Drawing No. _____

Computed by DUM Checked by EH Date May 7, 1931

Case IV (Over Flow Section)



MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Hank Fills Dam
Stability Analysis

Computed by DWM.

Checked by T. L.

S.O. No. 13333-22-ARA

Sheet No. 13 of 16

Drawing No. _____

Date May 7, 1931

Resultant of Hydrostatic Force on Upstream Face

$$\left(\frac{1.294 + 3.3}{2} \right) 32.1 = 73.730 \text{ Kips}$$

Resultant location =

$$\frac{\left[(1.294)(32.1) \right] \frac{32.1}{2} + \left[\frac{1}{2}(3.3 - 1.294) 32.1 \right] \frac{32.1}{3}}{73.73}$$

$$= 13.715 \text{ FT above base level}$$

Resultant on Downstream Face

$$.6(12.1)(.0625) = 0.454 \text{ Kips}$$

$$\text{Resultant Location} = \frac{.6(12.1)}{3} = 2.42 \text{ FT above base level}$$

Resultant Uplift Force

$$\left(\frac{3.3 + .756}{2} \right) 22 = 44.616 \text{ Kips}$$

Resultant location

$$\frac{\left[(.756)(22) \right] \frac{22}{2} + \left[\frac{1}{2}(3.3 - .756)(22) \right] \frac{22}{3}}{44.616}$$

$$= 8.7 \text{ FT FROM Upstream Face}$$

$$22 - 8.7 = 13.3 \text{ FT FROM Downstream Face}$$

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Houk Falls Dam
Stability Analysis

S.O. No. 13889-03-AREA

Sheet No. 14 of 16

Drawing No. _____

Computed by DWH

Checked by TL

Date May 7, 1931

Bearing Pressure (excluding Uplift)

$M_c \Rightarrow r$

$$r = \frac{73.73(13.715) - .454(2.42)}{82.845}$$

$$r = 12.193 \text{ FT}$$

$$12.39 - 12.193 = .197 \text{ FT FROM DOWN STREAM FACE}$$

$$e = 2\frac{1}{2} - .197 = 10.803$$

Bearing Pressure at toe

$$\frac{1}{2} [3(.197)] \text{ CL}_a = 32.845$$

$$BP_a = 280.355 \text{ KSF}$$



Excluding Uplift

280.355 KSF

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Hock Falls Dam

Stability Analysis

S.O. No. 13883--ARA

Sheet No. 15 of 16


Drawing No. _____

Computed by DWM

Checked by TS4

Date May 7, 1981

Resultant Loadings



Overturning

$$E M_A \Rightarrow \frac{82.845(12.39) + 0.454(2.42)}{73.73(13.715) + (44.616)(13.3)}$$

$$= \boxed{F.S. = 0.640}$$

overturning

Sliding

$$R = (38.229) \cdot 7 + 2(22) = 70.76$$

$$H = 73.73 - .454 = 73.276$$

$$F.S. = \frac{R}{H} = \frac{70.76}{73.276}$$

$$\boxed{F.S. = 0.966}$$

sliding

MICHAEL BAKER, JR., INC.
THE BAKER ENGINEERS

Box 280
Beaver, Pa. 15009

Subject Hank Falls Dam S.O. No. 15333-22-11A
Stability Analysis Sheet No. 16 of 16
Drawing No. _____
Computed by DCM Checked by TS Date Mar 7, 1958

Reaction Locations (including uplift)

(*)

$$\text{Case I} \quad \frac{\sum M_R}{\sum V} = \frac{32.2(10.7) + 22.07(14.67) - 82.845(12.39)}{82.845 + 22.07}$$

= 5.893 FT FROM TOE UNDER DAM NOT WITHIN MIDDLE THIRD

$$\text{Case II} \quad \frac{\sum M_R}{\sum V} = \frac{32.2(10.7) + 22.07(14.67) + 5(32.1) - 82.845(12.39)}{82.845 + 22.07}$$

= 3.252 FT FROM TOE UNDER DAM NOT WITHIN MIDDLE THIRD

$$\text{Case III} \quad \frac{\sum M_R}{\sum V} = \frac{58.469(12.945) + 36.3(13.402) - 82.845(12.39) - 1.92(.952)}{36.3 - 82.845}$$

= -3.79 FT FROM TOE NOT UNDER DAM SECTION

$$\text{Case IV} \quad \frac{\sum M_R}{\sum V} = \frac{73.73(13.715) + 44.66(13.3) - 82.845(12.39) - .454(2.42)}{44.66 - 82.845}$$

= -14.961 FT FROM TOE NOT UNDER DAM SECTION